

PLAT AND RECORD OF SURVEY No. 1279

Request of Robt. Kirk and Chas. H. Harder to set sec. cor. S 5 N. R 35 E.

Course	Degrees	Minutes	Chains	Links	Remarks
					Assisted by Robt. Kirk and O. A. Kirk, sworn chainmen.
					I find original Gov. cor. to secs. 8, 9 S 5 N. R 35 E, which is a charred post in ground, on N slope of hill, and under N.E. fence. Set over charred end of original post, a basalt stone 16 x 10 x 8 1/2 ins. mhd. 5 notches on South and 4 notches on East corners.
					Thence run South on random line bet Secs 8 & 9. 72. 21' E.
South	28	50			Ravine, course E.
				33	" " N.E. ascend.
				40	20 Gov. 74 sec. post, plain mound and pits; post, a palm mhd. iron. I summo the decayed post found and find lower end charred. At the point for cor. Set a basalt stone 16 x 10 x 6 ins. mhd. 5 on West.
					Thence ascend on random line 72. 21' E.
South	40	00			Set temp. cor. to secs. 8, 9, 16-17. Subgraphed for A. M. Isaac former owner of S 1/4 of sec. 16, who answers that he will send to locality of Gov. S 1/4 cor. sec. 16. S 5 N. R 35 E. Friday Nov. 11, 1887.
					(Nov. 14, 1887. A. M. Isaac comes upon the field, and points out and verifies the locality of said S 1/4 cor. of sec. 16 with which he has been well acquainted for the past 8 years. In digging to set stone at point verified by A. M. Isaac, I dug up bits of old decayed post, which I take to be cottonwood. Old ditch fence run N & E. from this point; Set here a basalt stone 15 x 11 x 7 inches mhd. 4 notches on E. and 3 notches on S. This cor. is several feet East of temp. cor. set yesterday.)
					Continuous random line: -
South	44	75			Ravine, N.W. - ascend
				108	50 Chas. R. Huber's house on line (S 6 cor)
				120	Set temp cor to secs. 16, 17, 20, 21; find no traces of orig. cor.
				160	" " 74 sec. cor.; find no traces of orig. cor.
				191	25 Set E & W line 108 lks. west of cor. to secs 20, 21, 28, 29, which is the original, mhd. cotton wood post, lying on the old Gov. line under E & W fence. I dig in center of mhd. and find charred end of post, over which I set a basalt stone 25 x 5 x 4 ins. 18 mhd. on

PLAT AND RECORD OF SURVEY No. 2719

Corn.	Degrees	Minutes	Chains	Links

ground mkd 4 notches on E and 2 notches on S. This cor is on W. hill side about 10chs. E. of ravine, course N.W.

On returning to pt of commencing, I find original Gov. cor. to secs 16-17-20-21, verified by A.M. Isaac, and which is decayed bits of old post in ground on gentle N.E. slope; old lines of ditch fencing run E. & N. from this cor. point, at which I set a basalt stone 15 x 11 x 7 ins. mkd, 4 notches on E. & 3 notches on S. (Nov. 14th 1887)

Geo. C. Arnold, County Surveyor

At proportionate distances and on true lines, I set a basalt stone 17 x 8 x 5 1/2 ins. 12 ins in ground for cor to secs. 8, 9, 16, 17, 21, 5 N. R. 35 E. mkd. 4 notches on S. & E. about 300 lks west of a ravine, course N.E.

Geo. C. Arnold, County Surveyor

Corners set in a survey for Dr. S. Jones and Dr. A. P. Burg, Sep. 12th 1857
Cor. for secs. 1, 2, 35th & 36, Tpo 3rd & 4th N. R. 30 E, which is the original post rotted off at ground and lying on a mound, in the center of which I find the lower end of said post, charred, and over which I set a stone 16 x 16 x 5 ins. mkd. 5 notches on W. and 1 notch on E.

The 4 sec. cor. bet. secs. 11th & 12th T 3 N. R. 30 E, which is the lower charred end of original post, in center of plain old earth mound & pit on west, over which charred end of post, I set a stone 15 x 7 x 4 ins. mkd. 4 on W.

Cor. for secs. 3, 4, 35th & 34 Tpo 3rd & 4th N. R. 30 E, which is the charred end of original post in old mound with top of original post lying by. I set over the charred end of post a stone 20 x 8 x 6 1/2 ins. (all under ground) stone mkd. 3 notches on E. & 3 notches on W and 6 notches on N. School house in canon bet. N 63rd 30 E about 20chs. dist.

Cor to sec 12, 11th & 12th T 3 N. R. 30 E, which is a stone 13 x 7 x 6 ins. 12 ins in ground, 5 notches on S and 1 notch on E. - Deposit piece broken gut bottle (glass) set as, per original notes

Cor to sec 7, 3, 35th & 35 Tpo 3rd & 4th N. R. 30 E, which is a stone 21 x 10 x 6 ins mkd. 6 notches on N. & 2 notches on E, on west hill side, at original cor. pt, as per original notes - found old md. & pits.

Geo. C. Arnold, County Surveyor.

Cours. Degree Minutes. Chains. Links.

Assisted by A. O. Kirk, and Robt Kirk, sworn chains and b. Harder and Chas. Harder, jun., sworn flagmen, with a British improved solar compass, adjusted to the sun's declination for Nov. 9th 1887, I commence at cor. for Secs. 4, 5, 8 & 9 S. 5 N. R. 35 E. I find original charred end of baln post in mound under fence, near residence of A. O. Kirk, on N. hill side, I set, here, over end of charred post a basalt stone 16x10x5 1/2 ins, marked 5 notches on S. and 4 notches on E. cor. I run, thence on random line bet. Secs. 8 & 9 var. 21° E.

- South 28 50 Ravine, course East.
- 33 00 " " N.E. Ascend hill.
- 40 20 Gov. 1/4 S. cor.; Original baln post, charred end, in mound with pits E. & W., on N. hill side. I set a basalt stone 16x10x6 ins. on E. side of 1/4 S. post, 1/4 cut on W. face of stone I continue random line, from this 1/4 S. cor. var 21°
- South Ascend about 10 chains to summit.
- 40 00 Set temp cor. for Secs. 8, 9, 16 & 17. Find no Gov. sec. cor. I continue random line bet. Secs. 16 & 17.
- 44 75 Ravine N.W. Ascend
- 80 00 Set temp 1/4 S. cor. bet. Secs. 16 & 17, near summit. Find no indications of Gov. 1/4 S. cor.
- 115 50 Chas. R. Huber's house; S.E. cor. on random line.
- 117 05 Int. E. & W. line 218 links west of cor. of old ditch lines running N. & E. at which point it is claimed that A. M. Isaacs & brother C. B. Isaacs, both in Pen^{ns}ylvania will swear to the original sec. cor. I send, by Mrs. Isaacs, by Chas. R. Huber. Continue random line
- 120 00 Set temp. sec. cor.
- 160 00 Set temp 1/4 S. cor. bet. Secs. 20 & 21. Find no original 1/4 S. cor.
- 191 25 Int. E. & W. line 108 links west of cor. for Secs. 20, 21, 28 & 29 I find, here, original cottonwood post, properly marked and notched, lying on mound under fence course E. & W.

PLAT AND RECORD OF SURVEY No. 1279

Comm.	Degree	Minutes	Chains	Links
-------	--------	---------	--------	-------

Idig in mound and find lower end of post well charred, I set, over charred end of post, a basalt stone $28 \times 8 \times 4$ ins., 18 ins deep. This cor. is on west hill side, about 10 chains E. of ravine course N.W.

Misses Isaacs Answer telegram, and Mr. Huber goes with back to Bendleton, for them. — Mr. A. M. Isaac appears in the field and identifies as per preceding notes commencing on P. 166 of this book, and which were written on the blank 166 + 167 pages of this book, not knowing, at the time that I had commenced the notes of this survey on P. 168.

Jno. C. Arnold, County Surveyor.