

PLAT AND RECORD OF SURVEY No. 3019

Request of Charles Stanton, et al. May 22 1888

To reestablish $\frac{1}{4}$ sec. cor. bet. sec. 9 & 16 Sp. 5 & 7 R. 33 & N. 7.

Course	Degrees	Minutes	Chains	Links	Description
					Ascend at N.E. cor. sec. 16, T. 5 N. R. 33 E., which is a boulder set by H. J. and G. L. Stockman, by old original sec. post, in mound in center of intersection of lanes N.E.S. and S.W. Turn thence on random line; descend. to a 21°
SW	55	30	34	30	Int. R. R. track at foot of hill; course of track NW & SE.
			35	23	Int. N. & S. line 50 links north of point, claimed by B. U. Macy, and Effinger; Geo. Campbell and others to be original $\frac{1}{4}$ sec. cor. Stake to mark point, and continue the random line
			37	30	Water channel, in Tansyelm cañon, course NW. Ascend. (con)
			40	00	Set temp $\frac{1}{4}$ sec. cor. in N. edge of upper grade; find no traces of post
			40	50	Summit; descend.
			41	70	Center of draw, course N.; ascend
			44	00	Summit.
			48	00	Descend.
			52	00	Water channel of deep ravine, course N.; ascend.
			75	66	Int. N. & S. line 19 links N. of plain mound and pits, with the original sec. post lying on the mound and marked for sec. 5, 9, 16 & 17 T. 5 N. R. 33 E.