

# PLAT AND RECORD OF SURVEY No. 13719

Request of D. W. Harris and W. W. McQueen, June 20, 1888.

To Reestablish  $\frac{1}{4}$  sec. cor. bet. secs. 11 & 12, T4 N. R. 36 E. W. M.

Course. Degree. Minute. Chain. Links.

Commence at acknowledged cor. to secs. 11-12-13-14 T4 N. R. 36 E. W. M., which is a stone in small stone mound on E. side of rail fence, course N. 7 S. I find portions of decayed post in mound, over which, I set a basalt stone 18x16x11 ins. mkd. 4 notches on S. and 1 notch on E. with + on top; from this cor. run on random line, bet. secs. 11 & 12. Descend.  $\text{ra. } 21^{\circ} \text{ E.}$

North

- 15 27 Dry gulch, course N.W. Ascend.
- 20 10 Fence bears E. & W. (nearly N.)
- 21 Summit; thence along hillside, near base, on E. side of ravine, (side near base.)
- 30 Descend abruptly.
- 40 Set temp  $\frac{1}{4}$  sec. cor.; find no traces of original  $\frac{1}{4}$  sec. cor. on which
- 49 05 Gulch, course about N. Ascend.
- 59 50 Summit. Descend.
- 60 Make stone mound for B. S.
- 66 Gulch, course N.W.
- 69 30 Small ravine, course W.
- 80 00 Set temp sec. cor.; find no indications of any other cor. near.
- 88 20 Fence bears, irregularly, E. & W.
- 92 62 Int. E. & W. line 2177 links W. of cor. to secs. 1, 2, 11-12, which is

the original sec. post, in fine state of preservation, in a mound of stones, on hill side facing N.W. and near summit. This cor. appears to be well authenticated, and is accepted without question; its location, as well as the cor. to sec. 11-12-13-14, can be shown to have been taken, without question, to be as found this time, on testimony of Harris, McQueen and others, since A. D. 1873.

Therefore, move temp  $\frac{1}{4}$  sec. cor. north 631 links, and then, East 1088  $\frac{1}{2}$  links and set a basalt stone 12x8x3 ins. mkd.  $\frac{1}{4}$  on West face, at south edge of small bench in steep hill side facing N., from which a tamarack 12 ins. dia. bears  $\text{N } 42^{\circ} 30' \text{ E } 260$  links (surface measure) dist.

Map on P.

J. E. McCoy and W. W. McQueen, sworn chmn. - Inst. used - a solar compass.

Survey made June 20, 1888.

Jno. C. Arnold, County Surveyor.