

PLAT AND RECORD OF SURVEY No. 64 19

By Request of Mrs Margelia McKay Aug. The 1st 1874

Course. Degree. Minutes. Chains. Links.

To Locate West Boundary Secs 6 & 7

T. 2 N. R. 33. E. W. M.



I commenced at the $\frac{1}{4}$ Sec. Cor. on West Boundary
 Sec. 6. on Range line bet. ranges 32nd & 33rd E
 which is a Stone 18 7/8 x 36 inches set in County Road N. N. S.

Thence I run South bet Secs 1 & 6 on Roubidoux
 Var $20^{\circ} 30' E$.

3 65 the $\frac{1}{4}$ Sec. corner on East Boundary, Sec. 1

6 00 County Road diverges to the right

7 70 head of Avale course S.W.

20 50 at temporary $\frac{1}{4}$ corner

23 80 the $\frac{1}{4}$ Sec. corner on East boundary of S. E. $\frac{1}{4}$ Sec. 1 12th 6th

25 00 foot of Hill enter Umataha river bottom

34 40 dry bed of Slough course west

40 36 I intersect 15 lbs west of the corner to Secs 6 & 7

Degrees Minutes Chains Links

- Which is a stone in mound of stone from which
- a Balm 7 ins dia brs N. 80° 25' E 62 1/2 lbs dist.
- " 7 " " " S 82° 50' E 73 " "
- thence N. 0.13' W on Lone line
- 186 Slough course wt.
- 196 north or right bank of Slough
- 1536 foot of hill and s.w. face of rocky hill
- 2018 set stake in mound of stone for No corner
- 3266 head of Draw course S 40° W
- 3436 county road from the s.w. extends north from this Point thence along center of county road.
- 3771 the 1/4 sec corner on East boundary Sec. 1
- 4036 the 1/4 sec corner on West boundary Sec. 6.

I commenced at the corner to Secs 6th & 7th
thence S 1° W on line

- 55 Slough course west.
- 365 the corner to Secs 1st & 12th T 2 N R 32 E S. 0.26' W on W. Bdy Sec. 7, S. 1, 2, N. R. 32 E.
- 1000 Slough at dam
- 1025 left or south bank of Slough course S 80° W
- 1235 Umarella river course S 80° W.
- 1410 left or south bank of Umarella river S 80° W
- 2224 Slough 40 lbs wide course west
- 2264 left or south bank of Slough
- 3360 O. B. & N. B. B. course N 80° W S 80° E
- 4410 the 1/4 sec corner on East boundary Sec 12 T 2 N R 32 E

John W. Kimbrell
County Surveyor.

Seary Kimbrell chismon
John Merris "