

# PLAT AND RECORD OF SURVEY No. 99

Surveyed for Jeff Nelly and Nelly Henry Hampton A B & C by Wm Egan and William for James John & John Lewis Clerk of Court  
 Henry Kinler Home being also others in House B & C Survey

Course. Degrees. Minutes. Chains. Links.

May 15 to June 24<sup>th</sup> 1898

Tp. 5, N. R. 36, E. W. M.

Tp. 5, N. R. 37, E. W. M.

Sec 2	Sec 1	6	5	4
Sec 11	Sec 12	7	8	9
Sec 14	Sec 13	18	17	16
Sec 23	Sec 24	19	20	21
Sec 26	Sec 25	30	29	28
Sec 35	Sec 36	31	32	33
Sec 2	Sec 3	6	5	4

T. 5, N. R. 36, E. W. M.  
 T. 4, N. R. 34, E. W. M.

T. 5, N. R. 37, E. W. M.  
 T. 4, N. R. 32, E. W. M.

## PLAT. AND RECORD OF SURVEY No. 747

15.00 I commenced at the original corner to Secs 12-19-13 & 24  
on the Range line between Tps 5 N Ranges 36 & 37

Hence I run South on Boundary line bet Secs 19 & 24

Var  $19^{\circ} E$

Assisted by J. E. Meeks and A. F. Herbaugh Chairman  
and Henry Stampses Flyman

Second

20 00 set temporary  $\frac{1}{4}$  sec corner

27 50 rising branch course SW

28 25 ascend steep N.W. hillside

40 00 could find no  $\frac{1}{4}$  sec corner set temporary  $\frac{1}{4}$  sec cor.

51 00 foot of Hill

52 50 Road NW  $\frac{1}{4}$  S E

62 50 Walla Walla river North fork 50 lbs wide course NW.

63 00 ascend steep Hillside faces N

80 00 could find no sec cor but at 500 chains a point 200 lbs west of  
a stone 20 x 8 x 6 inches, that is probably the corner, but I  
extend my line South for a correction

40 00 could find no  $\frac{1}{4}$  sec corner

80 00 could find no corner to Secs 30-31-25 & 36 and extend my  
line South bet Secs 31 & 36

10 15 enter South fork Walla Walla river bottom

17 08 South fork of Walla Walla river 150 lbs wide runs NW

18 58 South bank Walla Walla river

40 00 could find no  $\frac{1}{4}$  sec corner set temporary cor.

50 00 ridge course N E

88 60 Intersect - 615 lbs west of  $\frac{1}{4}$  sec corner to Tps 4 & 5 North  
of Ranges 36 & 37 E as found by myself  
and L. A. Wilbur in 1893

Hence I run  $N 2^{\circ} W$  on true line

41 40 set Stone 25 x 18 x 5 marked  $\frac{1}{4}$  in end of Stone for  $\frac{1}{4}$  sec cor

82 80 set Stone in end of Stone at foot of vertical ledge of rock 50' high  
for cor to Secs 30-31-25 & 36

Course.	Degrees.	Minutes.	Chains.	Links.
---------	----------	----------	---------	--------

- Run 1 run  $N 2^{\circ} W$  on same line bet  $10 31 5 25$   
 41 40 Set Stone  $20 \times 8 \times 10$  for  $\frac{1}{4}$  ac cor in  $\frac{1}{2}$  of Stone  
 42 50 The Stone corner to  $10 19-20-24 8 25$  on steep hillside  
 facing  $NW$  so probably found on the East of first line  
 There  $N 2^{\circ} W$  on same line bet  $10 19 8 24$   
 41 50 Set Stone for  $\frac{1}{4}$  ac corner in  $\frac{1}{2}$  of Stone  
 62 25 Set Stone in  $\frac{1}{2}$  and  $\frac{1}{4}$  ac on steep hillside facing but for  $\frac{1}{4}$  ac  
 83 50 The corner to  $10 18-19-13 8 24$

From the corner to  $10 19-20-29 8 30$

Run West on same line  $10$  or being in light  
 $102 27^{\circ} S$

- 20 00 Set Temporary  $\frac{1}{4}$  ac corner  
 23 52 Wall Wall piece  
 40 00 could find no  $\frac{1}{4}$  ac cor Set temporary  $\frac{1}{4}$  ac cor  
 81 36 Intersect  $10$  to  $10 19-20-24 8 25$

There East on same line bet  $10 19 8 30$

- 40 68 Set Stone for  $\frac{1}{4}$  ac cor from  $10$  which  
 is cherry tree 4 inches dia  $10 S 76^{\circ} W 145-110$  dist-  
 marked  $\frac{1}{4}$  S. B. T.  
 61 02 Set Stone  $20 \times 8 \times 10$  for  $\frac{1}{4}$  ac corner in  $\frac{1}{2}$  of Stone  
 81 36 The cor to  $10 19-20-29 8 30$   
 There North on random line bet  $10 19 8 20$   
 $102 24^{\circ} S$

- 20 00 Set Temporary  $\frac{1}{4}$  ac corner  
 40 00 could find no  $\frac{1}{4}$  ac cor but at  
 42 20 Intersect  $\frac{1}{4}$  ac corner which is original  $10$  cor  
 in  $\frac{1}{2}$  of Stone marked  $\frac{1}{4}$   
 Hence I believe my line  
 36 00 odd runs west  
 40 00 could find no  $10$  cor to  $10 17-18-19 8 20$

Station	Degrees	Minutes	Chains	Links	Description
					Here West
23	58				run Suloh course S 20° W
41	46				Intersect the original 1/4 sec cor bet Sec 17 & 18
					Here West
13	20				Road N 6° E 8 W
16	70				Ridge S 8 W
19	57				Road S 8 W
20	03				Set temporary 1/16 cor
40	14				Intersect 165 lbs East of the cor to Sec 7-8-17 & 18 Here S 1° 44' 5" on true line
20	07				Set Stone for 1/16 cor
40	14				the 1/4 sec cor bet Sec 17 & 18
80	87				Set Stone in mound of Stone for corner to Sec 17-18-19 & 20
					East on random line bet Sec 18 & 19 Here 21° 5"
11	00				run line course S W
21	85				" " "
32	50				" " South
40	21				could find no 1/4 sec corner set temporary 1/4 sec cor
46	50				run line into South
75	50				" " S W
77	50				the cor to Sec 17-18-19 & 20 Here West on true line
39	75				Set Stone for 1/4 sec cor bet Sec 18 & 19 Here South on random line through center Sec 18
41	12				Intersect true S 8 W line through center Sec 19
82	61				the 1/4 sec cor bet Sec 19 & 20 West on random line through center Sec 19
20	00				Set temporary 1/16 cor
40	07				Intersect true N 8 E line through center Sec 19 well beyond gate
80	15				Intersect 250 lbs North of 1/4 sec cor on West half Sec 19

Course.	Degree.	Minutes.	Chains.	Links.
---------	---------	----------	---------	--------

These  $N 88^{\circ} 44' S$  are true line through center Sec 19  
 Var  $21^{\circ} 15' S$

40 07 Set Stone for  $\frac{1}{16}$  corner in center Sec 19

60 10 Set Stone in prod. of Stone for  $\frac{1}{16}$  corner in center Sec 19

80 15 Intersect  $\frac{1}{4}$  Sec line bet Sec 19 & 20

From the corner to Sec 19-20-29 & 30

South

12 42 River Bottom

14 74 Walla Walla river run NW with fork

20 33 Set Stake for an approximate line or for Frank Kelley.

From the corner to Sec 18-19-18 & 24 I run  
 North on random line for John Syle  
 on West boundary Sec 18

Var  $19^{\circ} S$

20 50 Set Temporary line corner

40 50 Can't find for  $\frac{1}{4}$  Sec corner but at

41 15 Intersect 46 lbs west of fence post that some settlers  
 claim to be where the  $\frac{1}{4}$  Sec cor originally was located  
 but I extend my line North

56 50 Spring branch course NW

80 71 Intersect 208 lbs East of the original cor for Sec 7-18-12 & 13

These  $S 1^{\circ} 29' S$  are true line

20 18 Set Stake for  $\frac{1}{16}$  cor point

40 35  $\frac{1}{2}$  Set Stake for  $\frac{1}{4}$  Sec point

60 53 Set Stone for  $\frac{1}{16}$  cor point

80 71 the cor to Sec 18-19-13 & 24

From the corner to Sec 7-18-12 & 13 run

East on random line bet Sec 7 & 18

Var  $23^{\circ} S$

20 00 Set temporary line corner

40 42 Intersect 42 lbs north of  $\frac{1}{4}$  Sec cor

Days Degree Minutes Chains Links

- 20 21 Set post for 1/16 acre point -  
 40 42 Run on to Sec 7-8-12 & 13  
 South on random line through Sec 18  
 Var 22° 6'
- 11 25 ravine runs west -  
 20 00 Set Survey 1/16 acre -  
 37 00 ravine runs west  
 40 00 Set Survey 1/16 acre -  
 60 00 set " 1/16 acre -  
 82 30 Intersect 227 lbs East of the 1/4 Sec corner bet Sec 18 & 19  
 Thence N 10° 27' E on true line  
 20 48 Set Stone for 1/16 acre in mid of Stone  
 40 85 the true E & W line through Sec 18  
 60 98 Set Stone for 1/16 acre in center NW 1/4 Sec 18  
 82 30 the 1/4 Sec corner bet Sec 7 & 18. This is the correction after the following  
 commencing at the 1/4 Sec corner bet Sec 17 & 18  
 1/2 run west on random line through center Sec 18  
 Var 21° 35' 6'
- 38 84 Intersect N & S line 188 lbs north of Survey stake having set  
 60 00 Set Survey 1/16 acre -  
 80 05 Intersect 255 lbs north of 1/4 Sec corner West -  
 Thence N 88° 11' 6" on true line  
 20 02 Set post for 1/16 acre  
 Thence north on true line by alignment through  
 center NW 1/4 Sec 18
- 17 25 Spring branch runs NW  
 17 80 into wall of barn thence through barn  
 20 00 Set Survey 1/16 acre  
 39 94 the 1/16 corner on N Bay NW 1/4 Sec 18  
 Thence south on true line through center NW 1/4 Sec 18

Course.	Degrees.	Minutes.	Chains.	Links.
---------	----------	----------	---------	--------

1997 Set Stone 5x8x6 inches Marked  $\frac{1}{4}$  & in door yard house N.B.  
from White

a Lombard paper 10 inches dia. bro. N21°3'W 156 lbs dist.  
a box Eldon 7 " " S88°45' E. 7 " "

East on random line through SW  $\frac{1}{4}$  Sec 18

2000 Set temporary  $\frac{1}{4}$  Sec 18

4003 Interest 233 lbs south of the  $\frac{1}{4}$  Sec 18 in center  
of  $\frac{1}{2}$  Sec 18

There S 88° 53' W on true line

2006 Set Stone in mid of Stone for  $\frac{1}{4}$  corner in  
center SW  $\frac{1}{4}$  Sec 18

4003 The  $\frac{1}{4}$  corner on W. Body SW  $\frac{1}{4}$  Sec 18

From the corner on range line to Sec 12-13-7 3/4

Then north on range line bet Sec 7 & 12

W 22° 30' E

1975 Road E & W

4000 Set temporary  $\frac{1}{4}$  Sec 18 as I could find no  $\frac{1}{4}$  Sec 18

8000 could find no  $\frac{1}{4}$  Sec 18-12-6 3/4

There north could find no corners but at

7850 Interest Center of Road E & W on top line 250 lbs  
west of Stone in Road and 790 lbs west of center of  
Road running south said by some to be his bet Sec 586  
but for indication of any corner, as I could find no  
person that was positive as to location of any corner in  
this locality I abandoned search, and added points  
as I indicated by fences long standing for corner for  
West Body Sec 6 3/4

From the corner to Sec 7-8-17 3/4 1 man

North on random line between Sec 7 & 8

N 21° E

475 Old road E & W

575 creek runs W.

## PLAT AND RECORD OF SURVEY No. 1119

- | Time | Degrees | Minutes | Chains | Links |   |
|------|---------|---------|--------|-------|---|
| 16   | 50      |         |        |       | Old ridge Road E & W  |
| 20   | 00      |         |        |       | Set Temporary <sup>1116</sup> corner  |
| 38   | 50      |         |        |       | Ran line NW   |
| 40   | 11      |         |        |       | could find no <sup>114</sup> sec cor  |
| 48   | 45      |         |        |       | Terminat of ridge cross NW  |
| 50   | 27      |         |        |       | Intersect - 90 lks East of cor to Secs 5-6-7 & 8<br>Three S 89° E on true line  |
| 40   | 14      |         |        |       | Set Stone 26 x 15 x 5 in. mid of Stone for <sup>114</sup> sec cor   |
| 60   | 21      |         |        |       | Set Stone in mid of Stone for <sup>116</sup> sec  |
| 50   | 27      |         |        |       | True cor to Secs 7-6-17 & 18<br>North through center Sec 7  |
| 40   | 74      |         |        |       | Intersect true center E & W line through Sec 7  |
| 81   | 48      |         |        |       | Intersect 15 lks East of <sup>114</sup> sec corner point between 6 & 7<br>West on random line through center Sec 7  |
| 4    | 50      |         |        |       | Spring branch runs NW   |
| 35   | 00      |         |        |       | road NW & S E   |
| 41   | 75      |         |        |       | True N & S line through center Sec 7  |
| 79   | 50      |         |        |       | Intersect - 469 lks North of <sup>114</sup> sec cor point on W of Sec 7<br>Three S 86° 27' E on true line through center Sec 7  |
| 37   | 75      |         |        |       | Set Stone for center Sec 7 mid pts SE corner<br>Three on meander line along Traveled Road from center Sec 7<br>East 87 <sup>1</sup> / <sub>2</sub> chs to center road three S 29° 35' E 92 chs three S 49° 38' E 250 chs<br>three S 60° 50' E 452 chs three S 49° 35' E 108 <sup>1</sup> / <sub>2</sub> chs three S 61° 16' E 527 chs<br>to a point 16 <sup>00</sup> chains North of corner to Secs 7-6-17 & 18 three north<br>24 <sup>1</sup> / <sub>2</sub> chs to NE corner of <sup>114</sup> Sec 7 three west 3301 chains to a<br>point in road called commencing point and 87 <sup>1</sup> / <sub>2</sub> chains East of<br>the center Sec 7 making 50 <sup>7</sup> / <sub>2</sub> acres North of Road in S.E. of Sec 7<br>I commenced at line tree on West slope of mountain on Sp line<br>18 00 chains West of the Standard corner to Secs 34 & 35 - 1" Standard<br>Parallel North Range 37 848 ac Set Sp 4 & 5 North<br>Three I run West on Standard line for the |



## PLAT AND RECORD OF SURVEY No. 1219

Course.	Degrees.	Minutes.	Chains.	Links.
---------	----------	----------	---------	--------

purpose of Testing this line west and also for the  
re-establishment of corners missing on this line west  
Var  $22^{\circ}30' \text{ E}$

+18 00

40 00 could find no 4<sup>th</sup> Sec end

67 75 Spring branch course NW

80 00 could find no cor to Sec 33 &amp; 34

these west

1 50 ridge North

5 25 Gulch NB

12 50 ridge NB

17 50 Gulch NB

23 00 Summit of ridge course NW

40 00 could find no 4<sup>th</sup> Sec corner

42 25 Gulch course SB

78 00 Gulch " SB

81 05 Intersect 250 W. South of the Published Standard corner  
to Sec 32 & 33 on Hillside facing to the SB

This corner has been accepted and it has the appearance  
of being the original corner established by Mr. Brown

I therefore run west from this corner

Var  $2^{\circ} \text{ E}$ 

7 75 Gulch course SB

16 70 The Closing corner to Sec 4 &amp; 5 S41° 6' 37" W 1/4

18 75 Summit of ridge course S

40 00 1<sup>st</sup> Temporary 1/4 Sec corner56 16 1<sup>st</sup> Temporary 1/4 Sec c.c. for N by Sec 5-60 00 1<sup>st</sup> Temporary 1/4 Sec <sup>Standard</sup> corner for South by S W 1/4 Sec 32

63 75 Road SB S NW

75 47 Intersect <sup>1/4 Sec into</sup> front - supposed to be Standard cor for Sec 31 & 32

79 00 with a Walla Walla mine NW

80 40 without of Wilson's corner on South side well within

three west in Standard line

## PLAT AND RECORD OF SURVEY No. 1119

- | Page | Original Number | Chain | Links  |
|------|-----------------|-------|--|
|      |                 |       | These west on South Bdy. Sec 31 on Standard line   |
| 38   | 25              |       | Intersect 25 lts north of 1/4 sec cor set by Lavin Galla Walla   |
| 40   | 00              |       | Set Surveying 1/4 sec Standard cor could not find original cor   |
| 75   | 10              |       | Intersect 40 lts south of Standard Tp & Range cor set by Lavin Galla Walla                                     |
| 80   | 75              |       | Intersect 235 lts north of True Standard Township and Range corner   |
|      |                 |       | These west on South Bdy Sec 36 T5N R36E  |
| 400  |                 |       | Spring branch runs North   |
| 40   | 00              |       | Set Surveying 1/4 sec cor could find no original 1/4 sec cor   |
| 44   | 00              |       | Road NW R 8 E  |
| 76   | 45              |       | Intersect 64 lts south of Standard corner for Sec 35 & 36  |
|      |                 |       | These S88° 47' E on True line  |
| 38   | 22              |       | Set Stone 22 x 14 x 4 for 1/4 sec corner   |
| 76   | 45              |       | to Standard Tp & Range corner  |
|      |                 |       | These East on Standard line on South Bdy Sec 31  |
| 39   | 92              |       | Set Post in mid of East for 1/4 sec cor  |
| 79   | 85              |       | Set Stone for Standard corner for Sec 31 & 32  |
|      |                 |       | 60 lts East of old pine stub which I am satisfied is the original witness tree as per. Surveyor's field notes. |
|      |                 |       | These N89° 43' E Standard line on South Bdy Sec 32   |
| 400  |                 |       | Walla Walla river runs NW  |
| 19   | 97              |       | Set Stone in mid of Stone for 1/4 sec cor on south of Sec 32   |
| 23   | 27              |       | Set Stone 20 x 10 x 8 in mid of Stone for Closing 1/4 sec corner for Sec 5 T4N R37 E NW cor                    |
| 39   | 92              |       | Set Stone 24 x 10 x 8 in mid of Stone for Standard 1/4 sec corner for Sec 32 T5N R37 E NW                      |
|      |                 |       | Commencing at Standard corner for Sec 31 & 32  |
|      |                 |       | Run North for Sec 31 & 32 on random line   |
|      |                 |       | Var 21° E  |
| 4    | 65              |       | Walla Walla river runs NW  |
| 13   | 57              |       | Foot of hill and road NW R 8 E. ascend   |

Course.	Degree. Minutes.	Chains.	Links.
---------	------------------	---------	--------

20 00 Set Survey  $\frac{1}{16}$  cor40 50 Set Survey  $\frac{1}{16}$  cor could find no  $\frac{1}{16}$  cor50 00 Set Survey  $\frac{1}{16}$  cor could find no corner to Secs 29-30-31 832

Set Survey Corner

These north bet Sec 29 &amp; 30

20 00 Set Survey  $\frac{1}{16}$  cor

30 30 Permitt P ridge course NW S &amp; S

40 50 could find no  $\frac{1}{16}$  cor

57 01 the corner to Secs 19-20-21 &amp; 30

these south on true line

41 75 Set Stone 20 x 10 x 6 in mid of Stone for  $\frac{1}{16}$  cor62 62 Set Stone 14 x 12 x 8 for  $\frac{1}{16}$  cor

83 50 Set Stone 21 x 12 x 8 for corner to Secs 29-30-31 832

these south on true line bet Secs 31 &amp; 32

20 57 Set Stone in mid of Stone for  $\frac{1}{16}$  cor41 75 Set Stone 28 x 16 x 5 for  $\frac{1}{16}$  cor in mid of Stone

83 50 The Corner to Secs 31 &amp; 32

I Commenced at the corner to Secs 5-6-7 88

in T. 4 N. 637 E. W. M.

these East bet Secs 5 & 8 over  $21^{\circ} 45' E$ 40 47 the  $\frac{1}{16}$  cor corner bet Secs 5 & 8

these north on true line through center Sec 5 - by alignment

Var  $20^{\circ} E$ 82 85 the  $\frac{1}{16}$  cor Closing Corner on North Side Sec 5 -

these south on true line

9 10 Road S &amp; N W

18 00 Set Stake on line

20 50 Walla Walla river right bank course NW

22 61 the  $\frac{1}{16}$  cor on South Bank Walla Walla river

East on random line through center Sec 30

10 00 Spring handle course N &amp; S

19 00 Spur P ridge course N W

Degrees	Minutes	Chains	Links	
33	00			walla walla wire case NW
38	78			center Sec 31
79	56			Intersect 505 lks South of 1/4 sec corner bet Secs 31 & 32 thence S 86° 04' W on true line
39	78			Set Stone in mid of Stone for center Sec 31 from which a pine & iron rod to S 12° W 31 lks dist- " 9 " " " N 66° 6' 42 " "
				North through center Sec 31
35	00			walla walla wire case NW
82	99			Intersect 585 lks West of 1/4 sec corner bet Secs 30 & 31 horizontally set or reestablished by survey East bet Secs 30 & 31 thence S 4° 10' W on true line through center Sec 31 to true center Sec 31 East on random line bet Secs 31 & 32
40	00			could find no 1/4 sec corner bet Secs 30 & 31
80	00			could find no 1/4 sec corner I extend my line East and could find no original corner until I reached the end of the fourth mile Intersect the corner to Secs 25-26-35 & 36 thence I set the 1/4 sec corner bet Secs 31 & 32 at 40 chs and the corner to Secs 29-30-31 & 32 80 chains from starting point - which was the corner to Secs 25-26-35 & 36 East on random line through center Sec 30
6	00			now 18° 0'
7	15			fence N & S
40	00			set temporary 1/4 corner for center Sec 30
80	80			Intersect 411 lks South of the 1/4 sec corner bet Secs 29 & 30 thence S 87° 4' W on true line
40	40			set Stone 21 + 10 + 6 for 1/4 corner in center Sec 30
00	00			to 1/4 sec corner on West side Sec 30

Course.	Degree.	Minutes.	Chains.	Links.
---------	---------	----------	---------	--------

I Commenced at the corner to Sec 18-19-13 & 24 on  
Range line bet Ranges 36 & 37 T 5 North  
thence West on random line bet Secs 13 & 24

W 21° 30' E

21 00 gulch S on

40 00 could find no 1/4 sec bet Township 1/4 sec cor

56 00 Gulch runs S 25° W

80 00 could find no 1/4 sec corner to Sec 13-14-23 & 24

bet Township corner

thence I extend my line West bet Sec 14 & 23

20 00 bet Township 1/4 corner 2125' gulch runs South

37 00 gulch runs S W

40 00 could find no 1/4 sec corner bet Township cor

60 00 bet Township 1/4 corner

80 60 Intersection 125' N of the corner to Sec 14-15-22 & 23

thence N 89° 33' E on true line

20 07 set Stone for 1/4 cor in mid of Stone

40 15 set Stone in mid of Stone for 1/4 sec cor

60 23 set post in mid of Stone for 1/4 cor

80 30 set Stone and old original Post with mound pile & c

for corner to Secs 13-14-23 & 24

thence East on true line N 89° 33' E bet Sec 13 & 24

40 30 set Stone 18+6+5 for 1/4 sec corner

thence South through center Sec 24

W 20° 45' E

40 00 bet Township 1/4 corner for center Sec 24

44 00 Walla Walla river runs N W

81 25 Intersection 1/4 sec corner point

thence East through center Sec 24 on true line of alignment

29 00 Walla Walla river runs N W

40 25 Intersection True N & S line through Sec 24

55 25 bet Township Fractional corner bet Mackay & Eggers

60 25 bet Township 1/4 corner

Time	Degrees	Minutes	Chains	Links	
51 00					Intersect $\frac{1}{4}$ sec corner on east $\frac{1}{4}$ sec 24 thence west on true line through center sec 24
20 37					Set Stone in mid of Stone for $\frac{1}{16}$ corner
25 46					Set Stone marked F.C. in mid of Stone for meadows $\frac{1}{16}$ corner
40 75					Set Stone for $\frac{1}{16}$ corner for center sec 24 thence I run west on random line through sec 23 Var $22^{\circ} 0'$
20 50					Set Surveyors $\frac{1}{16}$ corner
40 00					Set Surveyors $\frac{1}{16}$ corner for center sec 23
60 00					Set Surveyors $\frac{1}{16}$ corner
50 67					Intersect at the $\frac{1}{4}$ sec corner bet sec 22 & 23 thence I run south through center sec 23
19 00					North fork Walla Walla river
20 00					Set Surveyors $\frac{1}{16}$ corner
38 50					Intersect True $\frac{1}{4}$ West line through sec 23
52 00					Intersect 100 lbs Post of $\frac{1}{4}$ sec corner bet sec 23 & 26 thence N $043^{\circ} 0'$ on true line through center sec 23
44 00					Set Post for center sec 23
63 50					Set witness Post 50 lbs north of true corner on north bank of river from which an alder $2\frac{1}{2}$ in dia & 2 lbs north marked $\frac{1}{16}$ N.S. thence I run south through center $\frac{1}{16}$ sec 23
20 00					Set Surveyors $\frac{1}{16}$ corner
38 25					the $\frac{1}{16}$ corner in center $\frac{1}{16}$ sec 23 N thence north
19 12					Set Post for $\frac{1}{16}$ corner in center N $3\frac{1}{4}$ sec 23 thence I run north on random line through center sec 14 Var $21^{\circ} 30' 0''$
20 50					Set Surveyors $\frac{1}{16}$ corner
40 50					Set Surveyors $\frac{1}{16}$ corner
80 50					Intersect 125 lbs west of the $\frac{1}{4}$ sec corner bet sec 11 & 14

Course.	Degrees.	Minutes.	Chains.	Links.
---------	----------	----------	---------	--------

Thence 1/4 m. S 53° W on true line

40 47 the center

60 53 set Stone 12+6+4 for 1/4 corner

Thence 1/4 m. West on random line through center sec 14

for 21° 40' S

40 20 intersect true line N 8° E through center sec 23

60 00 set Survey 1/4 corner

80 57 intersect 25 1/20 north of the 1/4 sec corner set sec 14, 15

Thence 1/4 m. S 89° 57' E on true line

20 08 set Survey 1/4 corner point

thence south on random line through center SW 1/4 sec 14

20 00 set Survey 1/4 corner

40 20 intersect 1/4 corner

thence north

20 10 set Stone in NW corner west side of 1/4 corner

I commenced at 1/4 corner in South 1/4 Sec 14

thence north through center S 1/4 sec 14

20 00 set Survey 1/4 corner

41 10 intersect 30 1/20 west of the 1/4 corner in center S 1/4 sec 44

thence south on true line

20 05 set Stone 20+10+4 for 1/4 corner in NW 1/4 Stone

40 10 the 1/4 corner on S side S 8° E 1/4 sec 14

I then proceeded to the corner to Secs 23-24-25-26

and ran south on true line by alignment set Sec 25-26  
to the standard corner to Secs 35-36 2 mile point

20 00 set Survey 1/4 corner all corners on this line are said to be set

25 00 gulch was NW and I find this to be the corner

40 00 set Survey 1/4 sec

47 00 walk under line, run NW

60 00 set Survey 1/4 corner

80 00 gulch was N 10° E

Time    Degrees    Minutes    Chains    Links

- Set Survey corner for Secs 25-26-35 & 36  
 Thence South on extended line
- 10 00 Set Survey  $\frac{1}{4}$  Sec cor —
- 90 35 The Corner to Secs 35 & 36 on 1" Standard parallel North  
 Thence North on true line bet Secs 35 & 36  
 Cor  $22^{\circ} 0'$  9036/4
- 10 50 Road E & W
- 42 59 Set post with mound and pits for  $\frac{1}{4}$  Sec cor —
- 45 17 Set post for corner to Secs 25-26-35 & 36  
 from which a  
 a cottonwood 10 ins dia to west 40 lts dist  
 thence North bet Secs 25 & 26
- 21 29 Set post in mid of Stone for  $\frac{1}{16}$  Sec cor
- 42 59 Set Stone 23 + 15 + 4 for  $\frac{1}{4}$  Sec cor in mid of Stone
- 63 88 Set Stone 24 + 8 + 6 for  $\frac{1}{16}$  Sec cor
- 45 16 The corner to Secs 23-24-25 & 26  
 Thence I run west on random line bet Secs 23 & 26  
 35 00 quest <sup>ms 3 W</sup>
- 40 50 25 lts South of mound said to be corner point
- 59 50 road NW N S E foot of hill
- 79 75 Intersect 75 lts South of the corner to Secs 22-23-26 & 27  
 Thence S.  $89^{\circ} 28'$  E on true line
- 39 82 Set Stone 20 + 10 + 6 for  $\frac{1}{4}$  Sec cor in mid of Stone  
 Thence I run South bet Secs 26 & 27
- 6 37 Walla Walla pine run NW
- 20 53 Set Survey  $\frac{1}{16}$  Sec cor
- 40 00 Set Survey  $\frac{1}{4}$  Sec cor
- 80 50 Intersect 25 lts East of the corner to Secs 26-27-34 & 35  
 Thence N.  $11'$  E on true line
- 40 25 Set Stone and post in mid of Stone for  $\frac{1}{4}$  Sec cor
- 60 37  $\frac{1}{16}$  Sec point on fence set stake not particular  
 only to keep point at present

1036/4  
 21  
 21  
 21



Course.	Degrees.	Minutes.	Chains.	Links.	
					Commenced at the corner to Secs 26-27-24 & 35-
					and run East on random line bet Secs 26 & 35-
					for $21^{\circ}30' S$
40 50					Set Iron peg $\frac{1}{4}$ Sec corner
00 00					Set Iron peg $\frac{1}{16}$ cor
79 50					Intersect 410 lbs south of the corner to Secs 25-26-35 336
					thence $S 87^{\circ}4' W$ on true line
19 87					Set $\frac{1}{16}$ corner & this in mid of Store
39 75					Set Stone and old post for $\frac{1}{4}$ Sec cor
79 50					the corner to Secs 26-27-34 & 35-
					thence South bet Secs 34 & 35-
20 50					Set Iron peg $\frac{1}{16}$ cor
25 00					Set Iron peg cor
40 50					Set Iron peg $\frac{1}{4}$ Sec corner
80 75					Intersect 12 lbs west of the Standard cor to Secs 34 & 35-
					thence North on true line bet Secs 34 & 35-
40 37					Set $\frac{1}{4}$ Sec corner point for subdivision of Secs
60 55					Set Stone for $\frac{1}{16}$ corner in mid of Store
80 75					the cor to Secs 26-27-34 & 35-
					thence 1/2 mile East on random line through center Sec 35-
					for $21^{\circ}6'$
39 90					Set Iron peg $\frac{1}{16}$ corner for center Sec 35-
59 85					Set " " " for center $\frac{1}{2}$ Sec 35-
79 80					Intersect 39 lbs south of the $\frac{1}{4}$ Sec cor bet Secs 25 & 36
					thence $S 89^{\circ}52' W$ on true line
					South on random line through center Sec 35-
20 50					Set Iron peg $\frac{1}{16}$ cor
41 00					Intersect true S & W line through center Sec 35-
82 80					Intersect $\frac{1}{4}$ Sec point on south side bet 35- obtained
					by running S on south side and established point
					thence North
41 20					thence center Sec 35-

- | Time  | By             | Notes  | Chain | Links |
|-------|----------------|--|-------|-------|
| 62 55 | Set Stone      | 20+10+0 for 116 cor in mid of Stone  |       |       |
| 82 50 | the 114 sec    | bet Secs 26 & 35-<br>Commencing at the 116 cor in entry of 6 1/4 sec 35-<br>1 run north on random line through N 8 1/4   |       |       |
| 20 00 | Set Survey     | 116 cor  |       |       |
| 42 10 | Intersect      | 50 ft east of the 116 cor on N by N 8 1/4 sec 35-<br>thence S 43' W on true line   |       |       |
| 21 05 | Set Stone      | in mid of Stone for 116 cor<br>North on true line by alignment through entry 26  |       |       |
| 40 50 | Set Survey     | 116 cor for entry sec 26   |       |       |
| 60 00 | Set            | " " " " " N 1/2 sec 26   |       |       |
| 82 50 | Intersect      | 114 sec cor bet sec 23 & 26<br>East on true line through entry sec 26 by alignment   |       |       |
| 20 50 | Set Survey     | 116 cor  |       |       |
| 39 65 | Intersect      | True N & S line 140 lbs. 1/2 north of first N 1/2 sec 26<br>thence west on true line   |       |       |
| 18 52 | Set Stone      | 20+6+4 for 116 corner<br>thence North  |       |       |
| 20 40 | Set Stone      | 18+6+4 for 116 cor<br>thence East on true line by alignment  |       |       |
| 19 53 | to true center | N 1/2 sec 26, Set Stone 12+6+5 for 116 cor<br>in mid of Stone<br>Commencing at the corner to Secs 25-26-35 & 36<br>1 run east on random line bet Secs 25 & 36<br>true 42° 6' |       |       |
| 20 50 | Set Survey     | 116 corner   |       |       |
| 40 50 | Set Survey     | 1/4 sec cor could not find old cor.  |       |       |
| 78 25 | The corner to  | Secs 25-36-30 & 31 on range line<br>thence west on true line bet Secs 25 & 36  |       |       |
| 17 56 | Set Stone      | for 116 cor  |       |       |
| 39 13 | Set Stone      | in mid of Stone for 1/4 sec cor  |       |       |
| 58 6  | Set Stone      | in mid of Stone for 116 corner   |       |       |

Course.	Degrees	Minutes	Chains	Links
---------	---------	---------	--------	-------

29 37

These North on true line through centre of Dec 25  
 by alignment - bet the lands of Chilling & A. Holden  
 To a Point on North or right Bank of water well known  
 these S 61° 35' E 5.62 chs. these N 59° 10' E 7.25 chs  
 " N 57° 10' E 7.32 " " S 55° 3' E 11.25 "  
 " S 54° 33' E 4.68 " " S 76° 37' E 1.74 "  
 " S 58° 20' E 16.61 " " S 60° 7' E 5.37 "  
 " S 43° 10' E 3.75 " " S 84° 23' E 6.25 "  
 to S E Corner 25 & S N 16 36 S W M. this is the  
 Land covered by Chris Hilberg in Dec 25 & S N 16 36  
 and contains 80<sup>50</sup>/<sub>100</sub> acres.

Sept 21<sup>st</sup> 1905  
 School Dist. No. 67  
 Corn at point in 1/4 Sec 36  
 of Dec 25 & S N 16 36 E W M  
 S 45° 58' E 10.85 chs dist  
 these S 45° 58' E 117.06 "  
 " S 56° 16' E 200 "  
 " S 60° 30' E 162 "  
 " West 100 " " to  
 N 67° W 218 " " to  
 Place of being ad bounding  
 acres  
 J. M. W. Kimbrell  
 County Surveyor

Commencing at the like corner on both boundaries  
 of Dec 36 I run North through centre of Dec 36  
 established true line S & S through centre Dec 36  
 thence 1 run E & West established a true E & W line  
 through centre Dec 36 and at the intersection of  
 this E & W and N & S true line I set Stone 20000  
 inches in mound of Stone for legal centre Dec 36  
 S 5 N 16 36 S W M

John W. Kimbrell county surveyor  
 with the assistance of  
 Shell Hopkins and Arthur Matzer as chainmen  
 and Chris Hilberg Louis Hilberg and Henry Shields as  
 layman and markers respectively

also J. E. Weeks and A. T. Hildreath chainmen  
 and Henry Stampico & Frank Leiby laymen  
 Chris Hilberg to a corner of 18 & 19 N 16 36 S W M  
 South 200 rods to point - 23° W 20 rods from corner of Dec 25 at foot of bluff 20000 inches  
 deep so may be marked W E 255° E 300 ft to datum so in 255° N E 400 ft to datum so in 255° W E 250 ft  
 to point - 29° W 100 ft from a corner of 18 & 19 N 16 36 S W M  
 S 50° 45' E 200 ft to datum so in 255° W E 400 ft to datum so in 255° W E 400 ft  
 S 40° 35' E 200 ft from southeasterly 550 ft more or less to S E on Dec 25 then run N 65° W 200 ft  
 leads to place of being bounding 400 acres more or less L. A. Wilson