

Acres. Minutes. Chains. Links.

Survey made on request of D. Johnson and
E. Pierson. Nov. 16, 1900.



Beginning at original fork. Cor the 1/4 Sec corner
on Township line on South line of Sec 35 of
T. 6. N. R. 31. E. W. 4. Thence N on random line
through center of Sec 35. $\text{Ta. } 21^{\circ} \text{ E.}$

40.00 Set 1/4 Sec Center Cor fork.

80.00. Intersect North line of Sec 35. 9.5⁰/₁₀₀ links E of
1/4 Sec Cor. between Sec. 35 and 36. Thence South
on true line through center of Sec 35.
 $\text{Ta. } 21^{\circ} 41' \text{ E.}$

40.015 Set fork on center line of Sec 35

80.03. 1/4 Sec corner on South line of Sec 35.

Beginning at fork Center of Sec 35 Thence
West at right angles from N & S. center line
of Sec. on random line.

41.30 Intersect West line of Sec 35. 60 links North
of Stone. original 1/4 Sec Cor of Sec 34 and 35.
Thence West on random line as above
on center line E & W of Sec 34.

PLAT AND RECORD OF SURVEY No. 127

Courses.	Degrees	Minutes	Chains	Links
----------	---------	---------	--------	-------

- 50 00 Could find no trace of East Corner remaining
- 160 60 Could find no trace of " " "
- From this point at right angles from last mentioned random line I run north
- 39 80 To a Town of intersection of North boundary line of Sec 33. 109 links E of Cor to Sec 28, 29, 32nd, 33. which corner is marked by Original State projecting about 4 inches above the ground and in a good state of preservation. Thence N. on 21st 30th E. on random line bet Sec 28th & 29.
- 40 00 Could find no remains of 1st Sec Cor and 2nd State for Sump 14 Sec Co bet Secs 28th & 29.
- As Wm Johnson and Pearson did not care to have accurate Survey made of lines outside of Sec 35. I made no further correction of them.

E. Pearson } sworn chainmen
 D. Johnson }
 H. O'Donnell. } Flagman

I hereby certify that the foregoing are true and correct notes of survey as made by me for 1847, 1850.

L. E. Macomber,
 County Surveyor