

Surveyed for Logan Saunders March 24th 1890

By J. W. Kimbrell County Surveyor Plat No 105

I commenced at the 1/4 Sec corner between Sec 11 and 14

thence South through center of Sec 14

Var 21° E

J 9 S 16 46 E W 0 M



- 20 00 Set Temporary 1/16 corner for center of N 1/2 Sec 14
- 24 27 Wire fence S 78° W
- 25 71 " " S 78° W
- 40 00 Set Temporary 1/16 corner for center Sec 14
- 40 28 Wire fence S 78° W
- 41 05 rail fence S 85° E
- 60 00 Set Temporary 1/16 corner for center South 1/2 Sec 14
- 70 06 fence S.E. & N.W
- 80 68 Intersect E & W line 27 lks west of the 1/4 Sec corner bet Sec 14 and 23 This line would therefore have a bearing of N 10° W or 810° E in point of fact.

I then commence at the 1/4 Sec corner bet Sec 13 & 14 and run West through center Sec 14

Var 20° E

- 20 00 Set Temporary 1/16 corner for center E 1/2 Sec 14
- 39 93 Intersect line N & S line 34 lks North of the first Temporary 1/16 corner for center Sec 14
- 80 26 Intersect N & S line 68 lks North of the 1/4 Sec corner bet Sec 14 and 15 therefore I find the bearing of this line to be N 89° 31' E and S 89° 31' W.

Commencing at the 1/4 Sec corner bet Sec 11 & 14 Run East bet Sec 11 and 14

Var 20° E

- 20 00 Set Temporary 1/16 corner
- 40 21 Intersect N & S line 29 lks North of the corner to Sec 11 & 13 & 14
- 20 10 1/2 Set Stone for 1/16 corner
- 40 21 The 1/4 Sec corner bet Sec 11 & 14

Commencing at the corner to Sec 11-12-13 & 14 thence South bet Sec 13 & 14 Var 20° E

- 20 00 Set Temporary 1/16 corner
- 40 31 Intersect S line East of the 1/4 Sec corner bet Sec 13 & 14 N 07° E on line
- 20 15 1/2 Set Stone for 1/16 corner
- 40 31 The corner to Sec 11-12-13 & 14

Beginning at the 1/4 Sec corner bet Sec 11 & 14

South 80.13 Rods ^ 1
 East 80.04 Rods ^ 2
 S 78° W 132 Rods ^ 3
 North 106 3/4 " ^ 4
 East 49 " to place of Beginning
 containing 35 33/100 acres

John W. Kimbrell

County Surveyor