

25 N 16 31 6 W M

Chains Links

From the 1/4 sec cor on North boundary Sec 2 1/4 mi
West on N Body Sec 2

4000 set survey cor for Sec 2-3-34 135-

81 20 a point 92.66 South of Old 1/4 Sec cor bet Sec 3 & 34
thence S 89° 20' E on true line

40 60 set post dug pits NB-SB-SW & NW 5 feet dia
and raised mound for cor to Sec 2-3-34 135-
thence S 2° 38' E bet Sec 2 & 3

16 38 set survey 1/4 cor

36 38 " " 1/4 sec cor

56 38 " " 1/4 cor

76 38 a point 54.66 East of cor to Secs 2-3-108 11
thence S 2° 15' W on true line

2000 set post for 1/4 cor

4000 " " " 1/4 sec cor

6000 " " " 1/4 cor

N 1° 45' W through center Sec 3

78 84 the 1/4 sec cor on N Body Sec 3
East through center E 1/2 Sec 3

40 37 the 1/4 sec cor bet Sec 2 & 3
West through center SB 1/4 Sec 3

40 57 the 1/16 cor in center S 1/2 Sec 3

John W. Tomlinhell County Surveyor