

Survey for Clarence and Charles Brown Jan 29 '03

Chains Links

- From the N.W. corner of Sec. 2 T. 1 N. R. 31 E. W. Co. I ran south on random line
- 41 84 set ten $\frac{1}{4}$ sec. corners.
- 81 59 intersect 47 lks. west of Sec. cor.
N. $0^{\circ} 21'$ W. on true line
- 33 58 set an iron piece of old sulky plow for $\frac{1}{4}$ sec. corner.
- From the N.W. corner of sec. 2 I ran east on random line
- 20 00 set ten $\frac{1}{16}$ sec. cor.
- 40 00 " " $\frac{1}{4}$ " "
- 73 76 intersect 3 lks. north of corner
N. $89^{\circ} 56'$ W. on true line
- 39 85 set 2 in pipe $3\frac{1}{2}$ ft. long for $\frac{1}{4}$ sec. cor.
- 19 92 $\frac{1}{2}$ set ten $\frac{1}{16}$ sec. cor.
- From the corner to Secs. 2, 3, 10 & 11 I ran east on true line
- 20 00 set ten $\frac{1}{16}$ sec. cor.
- 40 00 " " $\frac{1}{4}$ " "
- 73 95 intersect 18 lks. north of Sec. corner.
N. $89^{\circ} 52'$ W. on true line
- 39 97 $\frac{1}{2}$ set pipe 4 ft. long for $\frac{1}{4}$ sec. corner.
- 59 96 $\frac{1}{2}$ " a piece of old sulky plow for $\frac{1}{16}$ sec. cor.
- From the corner bet sec. 1 and 2 I ran west on random line
- 40 00 set ten $\frac{1}{4}$ sec. cor.
- 60 00 " " $\frac{1}{16}$ " "
- 73 92 intersect 71 lks. south of $\frac{1}{4}$ sec. corner

Chain Links

From the $\frac{1}{4}$ sec. cor. bet. secs. 2 and 11 I ran north on true line
 37 97 intersect 10 lks east of corrected corner
 81 43 $\frac{1}{2}$ to $\frac{1}{4}$ sec. cor.

South on true line

41 46 $\frac{1}{2}$ set iron piece of walking plow for $\frac{1}{4}$ sec. cor.
 From the center of sec. 2 I ran west on true line
 20 01 set tem $\frac{1}{16}$ sec. cor.

From the center of the west $\frac{1}{2}$ of sec. 2 I ran north on true line

20 00 set tem $\frac{1}{16}$ sec. cor.
 41 59 to $\frac{1}{16}$ sec. cor.

South on true line

21 48 $\frac{1}{2}$ set 1 in. pipe 3 $\frac{1}{2}$ ft. long for $\frac{1}{16}$ sec. cor.

From the corner to secs. 1, 2, 11 and 12 I ran south on true line

20 00 set tem $\frac{1}{16}$ sec. cor.

40 00 " " $\frac{1}{4}$ " "

79 80 intersect 22 lks. E. of sec. cor.

N. 89° 50' E on true line

39 90 set tem $\frac{1}{4}$ sec. cor.

19 95 " 2 in pipe 3 $\frac{1}{2}$ ft. long for $\frac{1}{16}$ sec. cor.

From the corner to secs. 11, 12, 13 and 14 I ran west on true line
 40 19 to $\frac{1}{4}$ sec. cor.

From the $\frac{1}{4}$ sec. cor. bet. secs. 10 and 11 I ran east on true line

20 00 set tem $\frac{1}{16}$ sec. cor.

40 00 " " $\frac{1}{4}$ " "

intersect 12 $\frac{1}{2}$ lks south of $\frac{1}{4}$ sec. cor. bet. secs. 11 and 12

From the corner bet. secs. 2 & 11 I ran south on true line

20 00 set tem $\frac{1}{16}$ sec. cor.

39 36 intersect corrected east and west line 19 lks west of preliminary stakes

North on true line

19 89 set piece of old sulky plow for $\frac{1}{16}$ sec. cor.

From the corner to secs. 2, 3, 10 and 11 I ran south

Chains Links

- on random line
- 20 00 set ten $\frac{1}{16}$ sec. cor.
- 39 98 intersect 20 lks west of $\frac{1}{4}$ sec. cor.
N. $0^{\circ} 17'$ W. on true line
- 19 99 set old piece of sulky plow for $\frac{1}{16}$ sec. cor.
From the center of the north half of sec. 11
I ran west on true line
- 20 00 set ten $\frac{1}{16}$ sec. cor.
- 39 96 to $\frac{1}{16}$ sec. cor.
East on true line
- 19 35 set piece of old sulky plow for $\frac{1}{16}$ sec. cor.
From the corner to secs. 1, 2, 11 and 12 I ran east
on random line
- 20 00 set ten $\frac{1}{16}$ sec. cor.
- 40 00 " " $\frac{1}{4}$ " "
- 73 96 to section corner.
West on true line
- 39 38 set ten $\frac{1}{4}$ sec. cor.
- 53 37 set piece of old sulky plow for $\frac{1}{16}$ sec. corner.

The center of the N. W. $\frac{1}{4}$ of sec. 12 was found in the regular manner and a 2 in pipe 3 ft. long was set for the $\frac{1}{16}$ sec. corner.

A description of the operation for the setting of the said center of the N. W. $\frac{1}{4}$ of sec. 12 is found in the record of survey No. 276 for J. J. Beaumont Feb. 2 '03

J. W. Kimbrell Co. Surveyor
Geary Kimbrell Deputy

Assisted by C. H. Riman Chainman

Ed Swires " "

Clarence Brown flagman