

by request of John W. Brown March 3 1909

J. I. S. 16.33.0.

Chains Links

- Commencing at the corner of Acs 9-10-15 & 16
Thence west bet sees 9 & 16
- 40 00 set Temp 1/4 sec. cor
80 54 the corne of sees 8-9-16 & 17
Thence East on True line
- 40 27 set Stone for 1/4 sec cor bet sees 9 & 16
80 54 the corner of sees 9-10-15 & 16 Stone cor
Commencing at cor to sees 3-4-9 & 10
Thence West bet sees 4 & 9
- 20 00 set Temp 1/6 cor
40 00 " " 1/4 "
- 80 86 the cor to sees 4-5-8 & 9
Thence East on True line
- 40 43 set Stone for 1/4 sec cor bet see 4 & 9
60 6 1/2 set Stone 20 x 10 x 8 for 1/6 cor
80 86 the cor to sees 3-4-9 & 10
South bet sees 9 & 10
- 20 00 set Temp 1/6 cor
40 00 " " 1/4 sec cor
- 80 62 the cor to sees 9-10-15 & 16
Thence North on True line
- 40 31 set Stone for 1/4 sec cor
60 46 set Stone for 1/6 corner
80 62 the cor to sees 9-10-15 & 16
North through center sec. 9

Chains Links

- 40 20 Set Sings $\frac{1}{16}$ cor
 80 74 the $\frac{1}{4}$ sec cor set No 4 & 5
 these South on true line
- 40 37 set Stone 10 x 6 x 6 for center sec 9
 80 74 the $\frac{1}{4}$ sec cor set No 4 & 5
 West through center $8\frac{1}{2}$ sec 9
- 20 00 set Sings $\frac{1}{16}$ cor
 40 34 the center sec 9
 North through center $N 6\frac{1}{4}$ No 9
- 40 34 the $\frac{1}{16}$ cor
 these South on true line
- 20 17 set Stone 11 x 8 x 7 inch for $\frac{1}{16}$ cor in center $N 5\frac{1}{4}$ No 9
 40 34 the $\frac{1}{16}$ cor in center $8\frac{1}{2}$ sec 9

John W. H. in Belle County Surveyor