

Survey for Cas. F. Harrison, Co. Co. Griswold and W. G. Purdy

July 27 '09

Chains Links

- From the corner to sees. 24 & 25 in T. 5 N. R. 28 E. W. Co.
and sees. 19 & 20 in T. 5 N. R. 29 E. W. Co. I ran north on true line
20 00 set ten $\frac{1}{16}$ sec. cor.
- 39 76 intersect $\frac{1}{4}$ sec. corner which is the original Government corner
marked by a pile of stones. I rebuilt mound of stone and marked a
basalt stone $20 \times 11 \times 6$ ins.
- South on true line
- 19 88 I set a basalt stone for $\frac{1}{16}$ sec. corner.
- From the S.E. corner to sees. 24 in T. 5 N. R. 28
E. W. Co. I ran west on random line
- 39 96 set ten $\frac{1}{4}$ sec. corner.
- 79 86 " " Set corner.
- 160 72 intersect 28 lks. S. of old original Gov. sec. corner.
- S. $89^{\circ} 94'$ E. on true line
- 80 86 I set ten sec. corner. and find several pieces of the old original
stake directly north of the temporary corner. and after diligent search and not
being able to find further evidence of old original corner I check on
previous survey of distance south to P.P. line and after measuring north
to the N.W. corner of sec. 24 I proportion the distance which
brings the corner within 2 lks of where the pieces of stake were found
Accordingly I set a basalt stone for corner to sees. 23, 24, 25 and 26
47 $\frac{1}{2}$ lks north of the erected ten corner.
- S. $89^{\circ} 34'$ E. on true line
- 39 96 set stone for $\frac{1}{4}$ sec. cor.
- From the corner to sees. 23, 24, 25 and 26 I ran north on random line
- 40 00 I set ten $\frac{1}{4}$ sec. cor.

Chains Links

80 05 intersect 56 lks west of old original Gov. Sec. cor.
S. $0^{\circ}24'$ W. on true line

40 02 $\frac{1}{2}$ I set stone for $\frac{1}{4}$ sec. corner.

From the $\frac{1}{4}$ sec. corner on the east. of sec. 24 I
ran west on random line

40 00 set tem $\frac{1}{4}$ sec. corner.

79 92 intersect 42 lks. S. of $\frac{1}{4}$ sec. cor.

N. $89^{\circ}42'$ E. on true line

39 90 set tem $\frac{1}{4}$ sec. corner.

From said corrected $\frac{1}{4}$ sec. corner in the center of sec. 24
I take a back sight on the $\frac{1}{4}$ sec. cor on the south of sec. 24 and
project the line north

39 90 intersect 18 lks west of old original $\frac{1}{4}$ section corner.

S. $0^{\circ}8'$ W. on true line

39 90 set basalt stone for $\frac{1}{4}$ sec. corner.

At S. W. corner of sec 19 T. 5 N. R. 23 E. W. Co. I find basalt
which I set on a previous survey. I corrected it for E. and W. measurement
and set the said tem. sec. cor. 100.00 ch. north of the township
line by previous survey from which I ran north on random line

20 00 set tem $\frac{1}{16}$ sec. cor.

39 84 intersect $9\frac{1}{2}$ lks E. of a point where I found some pieces of the old
original Government stake and after making further search
found rotted pieces of old stake in the ground. I marked
the place with a basalt stone for the $\frac{1}{4}$ sec. corner.

S. $0^{\circ}8'$ E. on true line

19 98 $\frac{1}{2}$ I set basalt stone for $\frac{1}{16}$ sec. cor.

J. W. Kimball County Surveyor.

By Geary Kimball Deputy

Assisted by W. G. Parry chainman

Zee Irving "

Chas. Sellers flagman