

RECORD OF SURVEY No. 303

Meadow Valley Land and Improvement Co

January 30 1910

Chains Links

2	1	2	1
2		- 1/4	1
3	4	5	4
		3/4	
2	1	2	1
3		- 4	
3	4	3	4

Commencing at the N E corner of Sec 36 T 4 N R 27 E W 4 M
thence west on South boundary No. 36

80 32 the corner of Sec 1-2-35 & 36

thence East on True line

20 05 set Post for 1/16 cu

40 16 " " " 1/4 sec cor

60 24 " " " 1/16 cu

80 32 the N E cor sec 36

thence North on East edge No. 36

20 06 set 1/16 cu post

40 12 the 1/4 sec cor on E edge sec 36

60 18 set 1/16 cu post

80 24 the corner of Sec 30-31-25 & 36 at this point I set Stone 20 x 10 x 8 in Place of Post

thence west set Sec 25 & 36

20 04 set Post for 1/16 cu

40 08 set Post for 1/4 sec cor

60 12 set Post for 1/16 cu

80 16 the corner to sec. 25-26-35 & 36 set Stone and post for cor

thence South set Sec 35 & 36 on True line

20 03 set Post for 1/16 cu

40 06 " " " 1/4 sec cor

60 09 " " " 1/16 cor

80 12 the corner to Sec 1-2-35 & 36

I now proceed to subdivide No. 36 by agreement into 40 acre tracts

setting Post 4x4 inches 3 feet long laying out 30 foot Street E & W and N & S through center

of Sec 36 also leaving 30 feet on N S & E W sides for 1/2 of Roads. Lots & Blocks

are Block No. 1 N 8 1/4 Block No. 2 NW 1/4 Block No. 3 S W 1/4 Block No. 4 S E 1/4 with least

1/4 acre 1-2-3-4 in each pt-

John W. Kimbrell County Surveyor