

The Maxwell Land and Navigation Co. Feb. 15 1910

J. J. Billerbeck foreman Peter Greenan claimant
Carl Ore thought "

Chains Links

From the N.W. corner of sec. 5 T. 4 N., R. 29 E., S. 1 W. I ran east on a random line a point 2 1/2 chs. north of the north corner for sections 3 & 4 of said township and range
159.85 N. 89° 59 1/2' W. on true line on the north boundary of sections 4 & 5 of said township and range
39.89 set iron pipe for 1/4 sec. corner on the north of section 4 59.802 chs. at the sec. corner
79.74 set iron pipe for the north corner to sections 4 & 5; 99.77 chs. at the sec. corner
119.79 1/2 set iron pipe for 1/4 section corner on the north of sec. 5
139.82 set the section corner on the north of the N.W. 1/4 of section 5
From the 1/4 sec. corner bet. sections 4 & 5 T. 4 N., R. 29 E., S. 1 W. I ran west on a random line to section corner, 79.802 chs. a point 4 chs. south of 1/4 section corner, 120.10 chs. a point 2 1/2 chs. south of section corner
39.41 From the S.E. corner of section 5 I ran north on a random line to sec. 4 & 5
81.90 intersect 14 chs. east of section corner, Thence S. 0° 6' E. on true line
21.79 set the section corner, 71.83 chs. set iron pipe for 1/4 section corner
From the 1/4 sec. corner bet. sections 4 & 5 of said township and range I ran east on true line, 39.52 chs. to fence post said to have been placed at the center established as center of section by previous County survey. Thence west
19.76 set 1/2 section corner. From the 1/2 sec. cor. on the south of the N.W. 1/4 of section 4 I ran north on true line, 41.96 chs. to the section corner. Thence
21.39 set the section corner. From the 1/4 sec. corner on the south side of sec. 4 I ran north on random line, 82.40 chs. intersect 30 chs. west of 1/4 sec. corner
From the 1/4 sec. corner bet. sec. 4 & 5 of said township and range I ran west on true line 40.20 intersect true north and south line to the west of true corner on said north & south line. Thence N. 0° 15' E. on true line
20.06 1/2 set 1/2 section corner. 42.30 chs. to 1/4 section corner
From the 1/2 section corner on the center of the N. 1/2 of said sec. 5 I ran west on random line, 40.16 chs. intersect 26 chs. south of corner
Thence south 89° 38' E. on true line; 20.08 chs. set the section corner
80.48 From the S.E. corner of section 33 T. 5 N., R. 29 E., S. 1 W. I ran west on a random line to section corner, Thence east on true line 20.12 chs. set the section corner
40.24 set iron pipe for 1/4 section corner, 60.36 chs. set the section corner
From the N.E. corner of said section 33 I ran south on true line to section corner. Thence north on true line 20.01 chs. set the section corner
80.04 set iron pipe for 1/4 section corner, 60.33 chs. set the section corner
40.02 From the S.W. corner of said section 33 I ran north on random line to a point 109 chs. east of the N.W. corner of section 21 of said T. 5 N., R. 29 E., S. 1 W. Thence S. 0° 15' E. I set temporary corners at proportional distances
19.99 set tem. 1/2 sec. cor., 39.98 chs. set tem. 1/4 sec. cor., 59.97 chs. set tem. 1/2 sec. cor.
78.76 set tem. section corner, 99.95 chs. set tem. 1/4 sec. cor., 119.94 chs. set tem. 1/2 sec. cor.
139.93 set tem. 1/2 sec. cor., 159.92 chs. set tem. section corner, 179.91 chs. set tem. 1/4 sec. cor.
179.90 set tem. 1/4 sec. cor.; 219.98 chs. set tem. 1/2 sec. cor.; 239.90 chs. to section corner
From the N.E. corner of section 33 I ran west on true line to a point 80 chs. south of section corner. Thence N. 89° 25' E. on true line
160.76 set 1/2 section corner, 40.25 chs. set iron pipe for 1/4 sec. cor., 60.37 chs. at true corner
20.12 1/2 on line determined by north & south measurement set iron pipe for section corner
80.50 Thence east on true line 102.56 1/2 chs. at the sec. cor., 120.63 chs. at iron pipe for section corner
140.67 1/2 set the section corner. From the N.W. corner of section 33 of said township and range I ran S. 0° 7' E. on true line 19.99 chs. set the section corner
39.98 set iron pipe for 1/4 sec. corner; 59.89 chs. at 1/2 section corner
From the S.E. corner of section 21 of said township and range I ran west on random line to section corner. Thence east on true line 20.76 chs. to the section corner
160.65 set iron pipe for 1/4 section corner, 60.55 chs. set the section corner
40.33 set iron pipe for section corner. Thence east on true line
80.66 1/2 set 1/2 section corner, 40.55 chs. set iron pipe for 1/4 section corner
21.03 set the section corner.
60.88 1/2 From the S.E. corner of section 21 I ran north on random line to section corner, Thence S. 0° 2' W. on true line
81.05 intersect 6 chs. west of section corner, Thence S. 0° 2' W. on true line
20.01 set 1/4 section corner, 40.02 chs. set iron pipe for 1/4 section corner
60.04 set the section corner.
From the N.E. corner of Sec. 21 of said township and range I ran west on random line, 81.04 chs. intersect 77 chs. north of section corner.
40.52 Thence N. 89° 27' E. on true line 20.26 chs. set the section corner
set iron pipe for 1/4 section corner; 60.78 chs. set 1/2 section corner

21 42 5 1/2 NW 27 E

Sec 21, 28, 33 T 5 N - R 29 E

Chains Links

- From the N.W. corner of section 25 T. 5 N. R. 28 E. S. 1/4. I ran south on random line, 160.33 chs. to section corner.
 Thence north I set temporary corners at proportional distances
 20.04 set tem. $\frac{1}{4}$ sec. cor; 46.08 chs. set tem. $\frac{1}{4}$ sec. corner
 60.12 set tem. $\frac{1}{4}$ sec. cor; 80.16 $\frac{1}{2}$ chs. set tem. section corner
 100.20 $\frac{1}{2}$ set tem. $\frac{1}{4}$ section corner; 120.24 $\frac{1}{2}$ chs. set tem. $\frac{1}{4}$ section corner
 140.29 set tem. $\frac{1}{4}$ section corner; 160.33 chs. set section corner.
- From the N.E. corner of section 36 I ran west on random line
 481.32 set tem. section corner. Not being able after diligent search to find evidence of the exact location of any original Government corners in scale I commenced at the township corner at the S.E. corner of section 31 and ran north on random line
 240.00 set temporary section corner. Not being able to find any original Government corners on this route I proceeded to align my line on the only known corner in the vicinity viz: The $\frac{1}{4}$ section corner bet. sections 17 & 18 T. 5 N. R. 28 E. S. 1/4. as follows:
 Thence east 79.89 chs. set tem. section corner. Thence north I intersect 64 chs. west of the $\frac{1}{4}$ section corner bet. sections 17 & 18 of said township and range. Accordingly I corrected the position of my random line running north through the N.W. corner of said section 31 by moving the same west 18 chs., making the closing of my random line running west to the aforesaid corner 482.75 chs. or 146 chs. longer than the distance given by original field notes. Thence east I set temporary corners at proportional distances as follows:
 80.21 set tem. section corner; 160.93 $\frac{1}{2}$ chs. set tem. section corner;
 241.28 set tem. section corner; 321.79 $\frac{1}{2}$ chs. " " "
 402.34 set tem. section corner; 402.34 chs. set iron pipe at intersection of line previously determined by north and south measurement, for the S.W. corner of said section 25.
- From the S.E. corner of section 33 of said township and range I ran north on true line; 154.77 chs. to section corner
 Thence south 79.88 $\frac{1}{2}$ chs. set iron pipe and stone mound for N.E. corner of said section 33. Thence south on true line
 19.97 set $\frac{1}{4}$ section corner; 39.94 set iron pipe for $\frac{1}{4}$ section corner
 59.91 set $\frac{1}{4}$ section corner; 79.88 $\frac{1}{2}$ to section corner.
- From the N.E. corner of section 21 T. 5 N. R. 28 E. S. 1/4.
 I ran south on random line, 79.63 chs. intersect 2 $\frac{1}{2}$ chs east of section corner. Thence N. 0° 1' E. on true line
 19.91 set $\frac{1}{4}$ section corner; 39.81 $\frac{1}{2}$ chs. set iron pipe for $\frac{1}{4}$ sec. cor.
 59.72 set $\frac{1}{4}$ section corner.
- From the N.E. corner of section 21 I ran west on random line 40.29 intersect 2 chs south of $\frac{1}{4}$ section corner
 Thence S. 89° 59' E. on true line 20.14 $\frac{1}{2}$ chs. set $\frac{1}{4}$ section corner.

J. W. Kimbrell Co. Surveyor
 by Geary Kimbrell Deputy