

D. R. Goom Mar. 31 1910

Chains Links

- From the N.E. closing corner of Sec. 1, T. 4 N. R. 28 E., W. Co. I ran east on true line
- 74.58 to S.E. corner of section 31 T. 5 N. R. 29 E. W. Co. I hence west on true line
- 80.66 set S.E. corner of Sec. 36 T. 5 N. R. 28 E., W. Co.
- From the S.W. corner of said section 36 I ran north on random line
- 80.15 to a point 17 lks. west of the N.W. corner of said section 36 I hence S. 0° 1' W. on true line; 20.04½ lks. set N. section corner.
- From the N. section corner on the west side of the N.W. ¼ of section 36 I ran east on random line
- 80.26 intersect 33½ lks. N. of N. section corner. Hence N. 89° 46' W. on true line
- 20.06 intersect true north & south line through the center of the N.E. ¼ of said section 36, where I set N. section corner.
- 40.13 intersect N. & S. center line of said Sec. 36.
- 60.18 intersect true N. & S. center line of the N.W. ¼ of said section 36 where I set N. section corner.

J. W. Kimbrell Co. Surveyor  
by Gary Kimbrell Deputy