

Carnes Bros. and Others June 19 1913.

Chains Links

I commence at the S.W. corner of section 19 T. 1 S., R. 32 E. W. Gr. from which I ran north on random line.

40.00 set temporary $\frac{1}{4}$ section corner.

60.00 set temporary $\frac{1}{16}$ section corner

80.00 not being able to find any trace of old original section corner I set temporary section corner and proceeded north

120.00 I set temporary section corner.

159.77 I intersect 41. lks. east of section corner, which was a well defined mound where the fences intersected before road was opened. Near by we found the stone which had been knocked out and laying on the top of the ground with the marks of the section corner.

Thence I ran $S. 0^{\circ} 14' E.$ on true line

39.94 set pipe for $\frac{1}{4}$ section corner on the west side of Sec. 19.

79.88 set $1\frac{1}{2}$ in. pipe and mound of stone for section corner.

99.85 set pipe and mound of stone for $\frac{1}{16}$ section corner.

119.82 set pipe and mound of earth for $\frac{1}{4}$ section corner

159.77 to S.W. corner of said section 19.

From the N.W. corner of section 19 I ran east on random line.

20.00 I set temporary $\frac{1}{16}$ section corner.

40.19 I intersect 2 links south of $\frac{1}{4}$ section corner which is a well defined mound of stone.

$N. 89^{\circ} 58' W.$ on true line

20.09 $\frac{1}{2}$ set pipe for $\frac{1}{16}$ section corner.

40.19 to section corner.

From the $\frac{1}{4}$ section corner on the west of said section 19 I ran east on true line

20.00 set temporary $\frac{1}{16}$ section corner.

40.00 set temporary $\frac{1}{4}$ section corner.

I then continued on true line without chaining to $\frac{1}{16}$ section corner in the center of the east half of said section 19 which I found to be a stone set

2005 WILSON & PRODUCTIONS COMPANY, PHOENIX AND SCOTTSDALE, ARIZONA

Chains Links

at the corner of a fence running south and east therefrom
From the $\frac{1}{4}$ section corner on the north of said
section I ran south on true line

20.00 set temporary $\frac{1}{16}$ section corner

39.91 I intersect east and west center line of section 19, $18\frac{1}{2}$
links east of previously set temporary corner.

At the said intersection of true line I set a pipe and
mound of earth for $\frac{1}{4}$ section corner in the center of said
section 19. I then continue on true line south
without measurement to the $\frac{1}{4}$ section corner which is a stone
 $7 \times 8 \times 16$ in laying on the ground by the side of a post and
a hole in the center of said old mound.

From the testimony of Mr. Dick Waugh it appeared that the
stone had probably been moved when the fence was built and the fence
post set by the side of the place where the stone had been.

The place where the post and stone is was identified by Mr.
Waugh as being the identical spot where the original corner was.

From the $\frac{1}{4}$ section corner in the center of said section 19
I ran north on true line

19.95 $\frac{1}{2}$ where I set iron pipe and mound of stone for $\frac{1}{16}$ section corner.

From the $\frac{1}{16}$ section corner on the north, south, east and west
of the N.W. $\frac{1}{4}$ of said section 19 I ran true east and west and
north and south lines bisecting said N.W. $\frac{1}{4}$ and at intersection
of said bisecting lines I set a pipe and mound of stone for
 $\frac{1}{16}$ section corner in the center of the N.W. $\frac{1}{4}$ of
said section 19.

Geary Kimbrell
County Surveyor