

Survey of Sec. 14 T. 6 N.; R. 34 E. W.M.

Chains
Links

Survey for Chris Hellberg, Mrs. F. B. Morse Etal.

With myself and C.A. Underwood, as Chainmen.

Geo. Weatherman and Otto Hellberg-Flagmen.

Began at Mile stone-21- on State Line, Ran thence West.

8.81 to old closing cor. N.W. sec. 14 Stone & pits This cor. is 21 ^{1/2} N. of State Line. Ran thence S. 0°-49' W.

5.25 Spring branch course west.

11.31 Granite stone marked 1/4, Removed stone and dug under, found nothing to indicate original Gov. Cor. Replaced stone.
Ran thence S. 0°-32' E.40.69 Found old charred & decayed Stake, old accepted cor.
Set Stone 3 notches on South and 2 on East, bottle under.
At S.E. cor. sec. 14 found old Gov. cor Set Granite Stone 6"x8"x15" bottle under. Ran thence North on random along fence.

15.82 Creek.

40.00 Set temp. pt.

40.87 fence runs West. Made thorough search for cor. could find nothing.

52.26 intersect State Line 8.50 Ch. West of mile Stone-22-
Ran west from mile stone-22-

74.32 c. c. Wash. S.W. Sec. 14- Stone mon.

80.71 mile post-21- Large stone.

Ran East from mile stone-22-

5.96 c. c. S.E. Cor. 14- Stone mon.

66.47 Stone c. c. Cor. N.E. int. Sec. 13- Thence East

14.16 to mile stone-23-

Established closing Cor. on State Line for Cor. sec's. 13 & 14

T. 6 N.; R. 36 E. W.M. by proportionate distances East and West on State Line from closing Cor. N.W. Sec. 14- and closing Cor. N.E. Sec. 13-

Set stone 8"x8"x17" marked c. c. on South, bottle under.

77.70 East to closing cor. sec. 13-

78.29 West to closing cor. Sec. 14-

