

Survey for J. N. Burgess & Geo. Stangier.

Section 31, T. 1 S.; R. 32 E. W. M.

Conn Rountree } Chainmen. Geo. Stangier - Flagman.
 Marvin Hutchison }

April 6 1916.

Began at $\frac{1}{4}$ cor. on West side Sec. 31, which is a stone marked $\frac{1}{4}$, in fence cor.
 Ran thence South.

40.22 Found point of stake at intersection of old furrows E+W+N. Set stone + gun
 barrel. Ran thence East, on South line of Sec. 31,

120.30 a point 131 ks. South of Stone $\frac{1}{4}$ cor. Stone marked $\frac{1}{4}$ on North.

Returned to S.W. Cor. Sec. 31, ran thence, N. $89^{\circ}56'$ E. on true line.

40.18 Set Stone $\frac{1}{4}$ cor. a stone $30 \times 20 \times 3$ - 18" in ground marked $\frac{1}{4}$ on North.
 Ran thence North, on center line Sec. 31.

80.23 a point 21 ks. East of N. $\frac{1}{4}$ Cor. which is buried stake and old iron
 at fence cor. Set stone marked $\frac{1}{4}$ at this point.

Ran thence East on North line Sec. 31.

40.26 Cor. Sec's 29-30-31-32 this stone was out and I replace it at intersection
 of old fence rows, where I find old post ends. Thence South.

40.16 $\frac{1}{4}$ Cor. a stone marked $\frac{1}{4}$ on East. Thence East on center line.

40.25 intersect N+S, center line 40.10 From S. $\frac{1}{4}$ Cor. $\frac{2}{3}$ 40.13 From N. $\frac{1}{4}$ Cor.

80.36 $\frac{1}{4}$ Cor. on West side Sec. 31. Set center sec. 31 at intersection
 of true N+S $\frac{2}{3}$ E+W, center lines. Set stone +

Recorded, April, 29, 1916.

Willard Bradley
County Surveyor.

Map on page 287

