

RECORD OF SURVEY No. 416

Survey for Fred Hascall by J. B. Runyan.

SPERRY, GLASS & FRYHOVER COMPANY, PRINTERS AND PUBLISHERS, TOLEDO, OHIO

Chains Links

Sec. - 18 - Tp. 2 S - R 32 E. W. M.

Nov. 30th 1918

Beginning of the cor. to Sec. 18-19-13-24 which is a basalt rock 14 x 12 x 6 1/2 ins. set 10 ins. in the ground and was set by Arnold and is 2 1/2 lks. N. of Cor. set by Bradley and is accepted as the true corner by Mr. Hascall and Mr. Runyan, I run North

10 20

Stanley Creek

11.00

Cor. of Hascalls house.

15.00

Road NW-SE and bottom of hill.

Ascend.

40.00

a point 20 lks. N of 1/4 cor. set by Bradley.

60.00

set stake on N + S fence line from whence 1/16 cor. set by Bradley is North 9.93 chs.

Thence Due East staking line to N + S. fence in center of section. This line was agreed upon and accepted as the dividing line of their properties. (Hascall + Runyan)

From the point where East line intersects fence - the center of the section as set by Bradley bears S - 10.60 ch. and W. - 1.52 chs.

There is quite a dispute over the corners of this section. For reference see Map on page 287 of Survey 413-412 by Bradley. See Notes in red for this survey.

Quincy C. Perry
Deputy County Surveyor.
December 9-1918.

