

Survey for Carl Hemphill and Mr. Granger.

Base Line bet. Tp. 1 N. R. 33 E + 1 S R 32 E

Beginning at a rock marked III on E and III on W faces - set by Kimbrell on Base line and supposed to be the corner of Sec. 33-34 of Tp. 1 N R 32 E. I chain West.

17.95 point where C.C. of Sec. 3-4 of Tp. 1 S. R. 32 comes.

40.00 $\frac{1}{4}$ sec. cor. rock on S. of Sec. 33

Set inst. over cor. and sight on $\frac{1}{4}$ cor. W. and plunge telescope and run E

2.02 point where $\frac{1}{16}$ cor. for Sec. 30th would come.

20.00 a point 19 lks. S. of $\frac{1}{16}$ cor.

40.00 a point 32 lks. S of $\frac{1}{4}$ cor.

60.00 a point 40 links. S. of $\frac{1}{16}$ cor.

62.12 a point 48 links S. of C.C. of Sec. - 2-3 on South.

80.14 a point 44 links S. of Sec. Cor. - 34-35.

The Gov. did not set a rock for cor. to sec. 33-34 so rock Kimbrell set should go 15 links north. Chained north from this cor. rock.

89.87 rock supposed to be $\frac{1}{4}$ cor. set by Kimbrell.

Feb. 21-1917.

Dug down at point 15 lks. N. of rock set by Kimbrell in 1863 for cor. to Sec. 33-34 and found point of old cotton wood stake set by Gov. surveyors. This then is the true corner so I move the rock 15 lks. North and reset it at this point - Rock 6" x 6" x 14"

Chained 17.75 west from cor. and dug to find stake. Couldnt find it so I set a rock 8" x 10" x 14" marked III on W and III on E for. C.C. to Sec. 3-4 - Tp. 1 S R 32 E.

Starting at $\frac{1}{4}$ sec. Cor. on S. of Sec. 33 I run west on line ~~west~~.

40.00 and set rock 8" x 8" x 15" in ground marked III on W and III on E for sec Cor. to Sec. 32-33.

62.00 set stake for Sec. Cor. 4-5 on South

80.00 Set stake for $\frac{1}{4}$ sec. Cor.

102.00 a point 30 lks. N. of point for $\frac{1}{4}$ cor. on N. of Sec. 5. Hence I went 1 mile S and chained thru 79.93 ch. and set rock 10" x 8" x 10" marked $\frac{1}{4}$ & buried bottle and can in hole.

I then corrected $\frac{1}{4}$ stake E of this cor. 19 lks. S and set rock 8" x 8" x 15" marked X

I corrected Sec. Cor. to Sec. 475 S-70 lks S. and set Rock marked III-III on E+W - 8" x 8" x 10"

Feb 15-21-1917

Aubrey F. Perry
County Surveyor