

Survey for W. J. Warman. Tp. 5 S. R. 34 E.

July 13-1921

Chains Links

Beg. at $\frac{1}{4}$ sec. rock $15' \times 9' \times 7'$ marked $\frac{1}{4}$ lot sec. 8-9. Tp. 5 S. R. 34 E. $49'$
 trees here $S 82^\circ E - 11$ links dist. and a $9'$ pine tree here $N 67^\circ W$. stake hit marked $85'$
 Hence I run a random line south

20 00 set line. $\frac{1}{4}$ cor.

40 00 looked for trace of old section corner. 8-9-16-17. Found bearing trees $S 87^\circ E - 12$
 and bearing trees $N 12^\circ W - 354$ links and at intersection of these rubus 3rd post
 $11'$ square and $4'$ ft. high - 2 ft. in ground for corner of sections 8-9-16-17

40. 12 a point 33 links east of true corner established from old bearing trees.
 I then went back and corrected $\frac{1}{4}$ cor. 6 links south and 17 links west and set
 a stake in mound of rubus for $\frac{1}{4}$ corner.