

Chains Links

Section 36 - Twp 6 N R 35 E W M

Survey was made to re-establish the $\frac{1}{4}$ section corner between Section 36 and Sec 36 Twp 6 N. R. 35 E. W. M.

Beginning at the ^{Township} section corner of Townships 5 N & 6 N Range 35 E ^{by old road} is a large rock plainly marked and buried in the road about 1 ft from the east wheel track and the being 3" under the surface and from which

A telephone pole blazed near the base with a stake tack in the blaze bears NW- 96 feet.

A telephone pole blazed near the base with a stake tack in the blaze bears SW- 44 feet and it is 4 feet north of the extended line of Miller's flume running east and west
Thence I run a random line West

2662 feet set temp point in road for $\frac{1}{4}$ corner.

5328 feet found mound of rocks partly destroyed at section corner of Section 1 & 2-35 & 36 at intersection fence line. As these measurements agree exactly with the survey notes of John Kirkell former County Surveyor who subdivided Sec 1 of Twp 5 N. R. 35 E. I set flags and both sides of road and got on line between by Betsey's house and line in $\frac{1}{4}$ section corner, and drove an iron bar 2" x $\frac{1}{2}$ " x 24" into the ground with the top flush for $\frac{1}{4}$ corner, from which North corner of concrete headwall for road culvert on west side of road is 11 ft. & North corner of concrete headwall for road culvert on east side of road is 24 $\frac{1}{2}$ ft.

Weather cloudy and cold, rainy.

Assistant - William Bloom.

November - 1927.

Paul H. King,
County Surveyor.