

Exteriors of T. 1, N., R. 34, E. W. M. Orc.

Chains North on E bdy of Sect. 13

80.00 Set basalt stone $20 \times 16 \times 10$ ins., 15 in in
the ground for cor to sects. 12, 13, 18, 7.
mkd. 4 notches on 5×2 on N edges.

North on east boundary of sect. 12.

17.75 Canon, course W

40.00 Table land. Stone $20 \times 9 \times 8$ ins., 15 in in
ground. mkd $\frac{1}{4}$ on W face

54.00 Wagon road, course E & W.

80.00 Set basalt stone, $18 \times 10 \times 8$ ins., 12 in in
the ground for cor to sects. 1, 6, 7, 12.
mkd 5 notches on 5×1 on N edges.

North on east boundary of Sect. 1

Leave table land.

40.00 Stone $18 \times 12 \times 12$ ins., 12 in the ground
mkd $\frac{1}{4}$ on W face

41.00 Gulch course N.W.

70.00 Summit