

10

10

N 89° 39' W bet secs 10, 15.

39.92 Stone 14x10x6" - 9" in ground mhd
1/4 on N face raised mound of stone.

79.84 to cor to secs 9, 10, 15, 16

North bet Secs 9 & 10

40.00 Post 3"x3"x36" - 24" in ground mhd
1/4 on N face. 18" Pine bears
575° W, 78 lbs mhd 1/4 S.B.T.

18" Pine bears N 57° E 66 lbs mhd
1/4 S.B.T.

80.00 Set basalt stone 12"x10"x8" - 8" in ground
mhd 5 notches on 5 x 3 on E edge.
mound of stone for cor. 3, 4, 9, 10.

West bet Sec 3 & 10.

40.12 Stone 12"x12"x12" - 8" in ground
mhd 1/4 on N face. 20" Pine bears
520° W 36 lbs mhd. 1/4 S.B.T.

24" Pine bears N 60° W 61 lbs mhd