

edges to cor to secs 7, 8, 17, 18,
mound of stone.

West bet secs 8 & 17 Var $18^{\circ}45'E$.

40.08 Basalt Stone $20 \times 12 \times 3$ " - 15 " in ground
mhd $\frac{1}{4}$ on N side from which a
 10 " Pine bears $N 83^{\circ}E$. 65 lbs
mhd $\frac{1}{4}$ S.B.T. a 12 " Pine bears $S 50^{\circ}E$
84 lbs mhd $\frac{1}{4}$ S.B.T.

80.17 to cor secs 7, 8, 17, 18.

$N 88^{\circ}55'E$ bet secs 7, 18.

43.30 set Stone $16 \times 10 \times 8$ ", 11 " in the ground
mhd $\frac{1}{4}$ on N, mound of earth.

83.30 to cor Secs. 7, 8, 17, 18.

North bet secs. 7 & 8 Var $18^{\circ}45'E$

40.00 Stone $14 \times 12 \times 12$ ", 9 " in the ground,
mhd $\frac{1}{4}$ on W face, mound of stone

80.00 Stone $18 \times 14 \times 14$ " - 14 " in ground