

Copy original field notes, Subs. T. 1 NR 34 E.

S 0° 17' W on true line bet. secs 1 + 2

- 29 800 Pendleton + La Grande wagon road, E + W.
- 31 40.62 Set Basalt 12 x 8 x 7. Pine 30 S 70° W 25 lbs. M.S.
- 31 55.70 Timbered gulch, S E - 150
- 31 80.62 Cor of 1, 2, 11 + 12,
- 31

S 0° 9' W on true line bet. secs 2 + 3

- 26.75 Pendleton and La Grande wagon road, + 50
- 80 40.87 Set Basalt 12 x 12 x 12 for 1/4 cor. M.S.
- 77.50 Gulch, S E - 300
- 80 80.87 Cor of 2, 3, 10 + 11
- 00

South on true line bet. secs. 3 + 4 Pa. 2 1/2° E

- 80 40.00 Set post. Pine 5 S 15° W 12, Pine 5 N 35° E 70
- 40 80.00 Cor of 3, 4, 7 + 10
- 60

S 0° 9' W on true line bet. secs. Hand 5 Pa. 20° E

- 23.50 Canyon, course W - 300
- 27.00 Point, course W. + 100
- 34.50 Canyon, course NW - 100
- 41.06 Set post. Fri 24 S 15° E 80, Fri 5 N 20° W 29