

Sub. T I N R 34 E

PG

36

North bet Secs 3 & 4

20. Set temp  $\frac{1}{16}$  cor. (Correction  $2\frac{1}{2}$  lks. S.  $4\frac{1}{2}$  lks. W)

39.95 Fall 9 lks E. of point for  $\frac{1}{4}$  cor. located by measuring  $N 15^\circ E$  12 lks from a pine tree 14 ins diam. marked  $\frac{1}{4}$  BT. Marks overgrown. I cut into this tree about 5 ins to uncover the marks. No trace of pine 5  $N 35^\circ E$  7 lks, described as bearing tree.

Oct. 8, 1917

Thence

West through center of Sec. 4

20 Set temp  $\frac{1}{16}$  (Correction 17 lks. W.  $19\frac{1}{2}$  lks. S)

20-17

40.1 Set temp  $\frac{1}{4}$  cor at center Sec. 4. (Correction  $34$  lks. W.  $39\frac{1}{2}$  lks. S)

40.34 Center of Sec. 4

to Set temp  $\frac{1}{16}$  cor. (Correction 37 lks. W.  $58\frac{1}{2}$  lks. S)

20.03 Set  $\frac{1}{16}$  cor.

40.06

~~30.40~~ Fall 78 lks. N. of  $\frac{1}{4}$  cor bet secs. 4 & 5

Oct. 9, 1917