

Sub T. 1 N R 3 H E.

44⁴⁵

From A-S. 7 run E.

20 Set 1/16 cor. (10 lks. N)

40.20 Intersect 1/16 cor at 11-S. 7. (10-17-17) ^{4 mi.}

From 1/4 cor bet secs 7+8 run West through center of Sec. 7.

20.21 Set 1/16 cor. Md Stone

40.42 Intersect P-S. 7. Set wooden stake in crevice in about 5 ft. above ground. S. face of ledge of rock about 15 ft. high, on steep slope and raise Md stone on top of ledge about 10 feet above cor. and about 4 feet NW of cor. Thence continue west on same line.

20.00 Set 1/16 cor.

Intersect 1/4 sec cor bet. secs 7+12 on west bdy of Tp. Oct. 20, 1917
1 1/2 miles

10-18-17

From Cor of ^{N bdy} T1 N R 3 H E. 41 S. 32 + 33 run West 5 + 32

20 Set 1/16 cor. (8 N)

37.00 Sulech. NW.

40.00 1/4 cor bet. secs 5 + 32 bears N 16 lks. dist

This is a basalt 9 X 7 X 6 in Md stone.

Thence West on same line

18.50 Up. + fence N 30° W

20.00 Set 1/16 cor

40. No trace of cor of secs. 5, 6, 31 + 32. (10 S-5 W)

40.05 Set Basalt 15 X 10 X 6 + raise Md Stone. W of cor. (Raise Md Stone)

50.10 1/4 cor bet, secs 6 + 31 bears S. 20 lks. (Stone in Md)