

36
1.89
40.00
40.80
41.12

From cor of 3+4 run East
Fence on line
C of Decs 33+34
Set
E. end of fence
Fence, South

41.15
.12
41.27
41.67 1/2
.40 1/2

41.15 Fence N. thence in plowed field
80. Set stake at pt. for cor of Decs 2+3
March 6. 1918.

Sec 10 From center sec 10 run track

14.01 RR
37.07 WC of 1/4 cor bet 3+10, which is
3.41 S. of true cor pt.
40.48 True cor pt. for 1/4 cor bet
3+10, on N side of river
Set Stone 16x8x8 for 1/4 cor bet
3+10. Mid stone.

Thence North through center sec 3

20. Set
30. Set
40. Set

41.31 Fence, E. m Set 1/4 cor at center

Fence cor
N. 1.2
W. 3.0

40.67 Temp 0 beans W. 13 lbs.
76.38 Pt for 1/4 cor on N body Sec 3 beans
(75.77) West 5 lbs

From C. S. 3 run S 89° E

132
36.59

20 Set stake
20.30 Fence, S.
40.20 Fence N+S
40.06 1/16 cor beans S. 5 lbs

From cor of 2.3.10 full run N.

20.20 Set 1/16 cor. WC 45 lbs. S+WC
45 lbs. N.

40.13 Fence, E. W. 54 lbs. W. of N+S fence
40.110 Set 1/4 cor.
76.57 Intersect cor of 2+3 on N body.

(75.84)

(75 lbs. excess) March 8

From 1/4 cor bet 4+9 offset North 23 chs
North, 23 chs.

Thence East

40.15 Offset South to point for cor of 3.4.9+10
as located by Mr. Wilkes, OK.

80.30 Offset South to point for 1/4 cor bet
3+10 as located by Mr. Wilkes

120.45 Offset South to cor of 2.3.10+11