

Mr. Isaac, says the old corner post was
in place when he set the gate post, and he
left the old cor post where it was.

Mr. Kimbrell + Mr. Isaac identifies
the cor of secs. 1, 2, 11 + 12 under
E-W fence, 30 lbs N + 30 lbs S
of Wilkes Corner.

Kimbrell says there was an old
fence running South from the
Corner. + Isaac says this old
fence, which was a leaning fence,
ran south from about 6 feet west
of the cor. I find remains of
old leaning fence from about 2 chs
to about 5 chs South, which
agree with Mr. Isaac's recollection
of the corner. Remains of fence are
greatly decayed and I find an old
cut 2' dia. spike in one piece.
Also find pile of stones where they

Locate the corner. 202
~~Along fence line to south find~~
~~ridge thrown up by plowing on West.~~
~~but land was not plowed on East.~~
~~This ridge agrees with statement of~~
Mr. Isaac says he plowed the land on
side of fence to south, about 1894
and threw the furrow against the
fence, but that the land on E of fence
was not plowed. I find the ridge
along old fence line, with indication
that land to W had been plowed, but
land to E had not. There is now
a fence running south from point
~~about~~ 20 feet west of the corner.

~~Find creek.~~